





First Lasing of





THE FERMI@ELETTRA PROJECT



FERMI is a Single-Pass, 50 Hz, Seeded FEL facility in the Soft X-rays:

☐ high peak power: from 0.3 to GW's range

short temporal structure: from sub-ps to 10 fs time scale

■ tunable wavelength: APPLE II-type undulators


variable polarization: horizontal/circular/vertical

✓ peak brilliance 10³⁰ – 10³¹ ph/sec/mm²/mrad²/0.1%bw

✓ flux $10^{12} - 10^{14}$ ph/pulse

√ bandwidth ~ Fourier Transform Limit

More details in M.Svandrlik poster **TUPB29**









Linac Layout





- □ 450pC 5ps flat-top bunch at the photo-injector ($\gamma \epsilon_n \sim 1 \mu m$),
- ☐ Some test on the Laser Heater but it will be optimized for
- FEL2 operation
- ☐ X-band cavity has not yet been installed



- □ Beam compressed @BC1 by about a factor 5 (BC2 not used up to now)
- □ Nominal energy @ linac end: 1.2GeV (reached 1.35GeV)

Seed laser / e⁻ beam RMS Time jitter ~ 100fs



1000



Design Goals & Achievements



2008	2009	201	2010		2011	
FEL2 Design Completion		-				
	Civil Engine	ering and Installations		Machine Upgrades		
		FEL1 Commissio	L1 Commissioning			
				FEL1	Operation	
	FEL2 final design	Infrastructures on time	FIRST LASING	Light Bean	to n Lines	
	Parameter	FELI	FEL2	Units		
γ	Output Wavelength (fund.)	65 - 20	20 – 4	nm		
	Peak Power	0.5 – 5	> 0.3	GW		
	Repetition Rate	10	50	Hz		
	Energy	1.2	1.5	GeV		
е	Peak Current (core)	200 - 300	800	Α		
	Bunch Length (fhwm)	0.7 - 1.2	0.7	ps		
	Proj. Norm. Emittance	3.0	1.0	mm mrad		
	Slice Energy Spread	0.20	0.15	MeV	* achieve	




COMMISSIONING



Injector ~2.5 months:


- 250pC 5ps flat
- First e-beam

- ■100MeV
- $\gamma \varepsilon_n = 0.9 \text{ mm mrad}$



Transfer line to Main Beam Dump ~1.5 months


- E=1.2GeV, Q=350pC, CF~3
- Defined the reference traj before installing und.
- time jitter grows from 150fs to 400fs when CF~5
- γε_n @1.2GeV ~ 4-5 μm




Linac and BC1

~3.5 months.

- 350pC 5ps flat
- Transport through the management linac
- First BC1 experiences





- 3 weeks for installing FEL 1 undulators
- 1.5 months of e-beam and seed laser commissioning







FIRST LASING AT 65-43 nm(Dec. 2010)



- The 1st seeded FEL output was observed at 65 nm, on 2010, December 13.
- 6 radiators tuned with calibration tables. e-beam compressed softly, ~100A.
- After spatial and temporal overlap of the seed laser (260nm, 160fs, 500 MW) with the e-beam, **seeded emission intensity overcame the spontaneous emission** by several orders of magnitude at the photodiode (~85 m far from the source point)



Shot-to-shot signal [a.u.] from atomic photo-ionization of Nitrogen at 10⁻⁵ mbar.



About 8*10⁸ photons per pulse (at **43nm**), equivalent to **6nJ**.







CHG seeded FEL measurements (Dec. 2010)




Seeded FEL mode has been possible and relative "easy" even if the electron beam was not fully optimized in terms of emittance and time jitter, and the photons diagnostics needed for FEL optimization was not completely available.






Validation of the mechanism: without optimizing too much, coherent up to the **15**th **harm. (17 nm)**!



Estimated FWHM ~ 33meV = $3 \times \text{Fourier limit (for } \sigma_t = 250 \text{fs)}$







Improvements of the FEL performance (5 months in 2011)



In order to improve the photons flux and the stability of the FEL light, we improved:

- ✓ electron beam time jitter
- ✓ photons diagnostics
- ✓ beam trajectory and optics matching in the spreader and undulator beamlines,
- ✓ electron beam emittance evolution along the machine;
- ✓ we increased the bunch charge to 450pC (5ps flat-top at the cathode): this required only a fine tuning of the photo-injector optics.






Projected Emittance along the machine @elettral



Note: Increasing the charge by 30% did not sensible deteriorate the emittance

Trasv. Wakefields effects were improved but not completely: we are going to install high energy deflecting cavity to optimize the beam traj in the linac








Time jitter




We found out that the main source of the electron bunch time jitter growth versus compression factor came from the RF phase jitter (estimated about 0.3° S-band). Acting on the LLRF parameters, the RF phase jitter was kept around 0.1° and we measured after the bunch compressor a time jitter of ~ 100fs (CF from 1 to 10).

Seed Laser "foot-print" in electron long. phase space provides indirect measurement of the time jitter between the laser and the electrons (~100fs)



Seed laser temporal delay scan vs FEL intensity provides information about the "active" temporal profile of the electron bunch








FEL at 52nm (Q=350pC, I ~ 200A)





(TEM00 mode)



100%





FEL obtained for Q=450pC, I~300A



* Photodiode saturates at	t~10 ¹³ photons
---------------------------	----------------------------

		•		
λ nm	Number of photons	E μJ	ΔE_{FWHM} meV	$\Delta E_{FWHM}/E$
52.5	>10 ¹³ (*)	>40	30	1.3*10 ⁻³
43.3	>10 ¹³ (*)	>45	35	1.2*10 ⁻³
32.5	>10 ¹³ (*)	>55	45	1.2*10 ⁻³
20	4*10 ¹²	40	50 100 shots	8*10 ⁻⁴ 100 shots







REF: M. Zangrando, C. Svetina


G. Penco 12


^{* *}Photodiode Calibration to be confirmed





Measured HGHG seeded-FEL spectrum Gelettral

















* Single shot spectrum

13

REF: M. Zangrando, C. Svetina




G. Penco




FEL at 20nm (FEL 1 goal)




FEL spot on the YAG ~47m far from the source point



FEL spot on the YAG ~54m far from the source point (divergence ~ 0.05mrad)



We used the 2nd order of diffraction of the spectrometer (transmission less than 10% wrt to the 1st order)








FEL variable polarization





More details in C. Spezzani talk THOBI1



G. Penco 15



Acknowledgments





POSTERS:

- ✓ MOPA03 Polarization Control of FEL Non-linear Harmonic Generation Emission
- ✓ TUPA05: Polarization Tunability at FERMI@Elettra. First Tests and Perspectives
- ✓ TUPB25: Full Tunability of a High-harmonic Source from Near-UV to XUV
- ✓ TUPB29: Status of the FERMI@Elettra Project
- ✓ WEPA03: Commissioning of the FERMI@Elettra Multi-purpose Electron Beam Diagnostics Station in the First Magnetic Compressor Area
- ✓ WEPB23: Coherent Ultraviolet Transition Radiation for Seeded FEL Bunching Optimization

TALKS:

- ✓ TUOC4: Design and First Experience with the
- **FERMI Seed Laser**
- ✓ WEOBI1: FEL Commissioning at FERMI@Elettra
- ✓ THOBI1: Polarization Control Experiences in Single-pass Seeded FELs
- ✓ FROAl2: All-optical Femtosecond Timing Distribution for the Fermi@Elettra FEL





Thank you



