

Superconducting Linac for the RISP (Rare Isotope Science Project)

Hyung Jin Kim
Institute for Basic Science Project

2014/06/18


IPAC14, Dresden, Germany

Collaboration with KNU, POSTECH, SNU, NFRI,
Vitzrotech, SFA, TRIUMF, IHEP



Rare Isotope Science Project (RISP)

- **Conceptual Design Study (2009.3 - 2011.2)**
- **Rare Isotope Science Project(RISP) launched (2011.12)**
- **Construction period: 2012-2021**
- **46B KW (~443M USD) from central government for heavy ion accelerator itself**
- **62B KW (~597M USD) from central government for buildings and tunnel construction**
- **39BKW(~375M USD) from central government for land purchase**



RISP – Bird Eye View



RISP – Bird Eye View


Accelerator	Driver Linac (SCL1-SCL2)		Post Acc. (SCL3-SCL2)
Particle	Proton	Uranium	RI beam (Sn-132)
A/q	1	7(+33.5)→3(+79)	7(+20)→3(+47)
Beam energy	600 MeV	200 MeV/u	180 MeV/u
Beam current	660 μ A	8.3 μ A	-
Power on target	> 400 kW	400 kW	-



05m²


Superconducting Linac

- RISP consists of Injector, SC Linac and IF systems.
- SC Linac comprises low energy linac (SCL1), charge stripper section (CSS) and high energy linac (SCL2).



SCL Characteristics

- Linac baseline frequency is 81.25MHz
- Niobium Cavities operating at 2K and 4.5K
- Focusing by normal conducting quad doublets
- Optimized geometric beta of SC cavities (0.047, 0.12, 0.30, 0.51)
- Employs larger aperture to reduce beam loss (4cm and 5 cm aperture)



Layout of Driver Linac

ECR	LEBT	RFQ	MEBT	SCL11	SCL12	STRIP	SCL21	SCL22
-----	------	-----	------	-------	-------	-------	-------	-------

QWR
(81.25MHz)

HWR
(162.5MHz)

SSR1
(325MHz)

SSR2
(325MHz)



22 cryomodules → Output 2.7 MeV/u

22 $\beta=0.047$ QWRs, 44 quadrupoles



13 cryomodules → Output 6.0 MeV/u



19 cryomodules → Output 18.5 MeV/u


98 $\beta=0.12$ HWRs, 64 quadrupoles

Stripper: charge state 33, 34 → 77,78,79,80,81 for Uranium



23 cryomodules → Output 56.5 MeV/u

69 $\beta=0.30$ SSR1, 46 quadrupoles




23 cryomodules → Output 200 MeV/u

138 $\beta=0.51$ SSR2, 46 quadrupoles

Total 331 cavities, 100 cryomodules, 196 quadrupoles, 122m (LEL,CSS), 181m (HEL)


Lattice Design

- Transverse emittance increase is less than 20%.
- Longitudinal emittance is improved.



Machine Imperfection Effects

- Beam centroid exhibits max orbit deviation of 8 mm.
- It is expected that beam loss will reduce with orbit correction.




Item	Quantity	Error	Distribution
Cavity	Misalignment	1mm	Uniform
	Tilt	5 mrad	Uniform
	Voltage, phase	1%, 1°	Gaussian
Quadrupole	Misalignment	0.15mm	Uniform
	Tilt	5 mrad	Uniform
	Magnetic field	1%	Gaussian


What is considered in RISP design

- Linac operation cost
 - The long-term operating costs of the accelerating linac are significant
 - Superconducting linac operating costs are dominated by the cryoplant and operating temperature.
 - RISP is focused on a superconducting linac design.
 - Components design is focused on optimization for reducing the cryogenic equipment and their operating costs.
- Linac hardware cost
 - Superconducting cavity, cryomodule and cryoplant are complicated and costly.


Optimization of Cavity Parameters



Mechanical analysis



Multipacting analysis



Frequency shift


Frequency shift	QWR
Resonant Frequency	81.25MHz
Cavity length(upper)	-67.1kHz/mm
Cavity length(lower)	+1.3kHz/mm
Welding (0.58mm shrink)	+38.2kHz
EP/BCP (125um)	+267kHz
External pressure(Vacuum, L-He)	-4.6Hz/mbar
Cool down(293K→2K)	+203kHz
Lorentz Detuning	-1.7Hz/(MV/m) ²

Superconducting cavity

QWR



HWR



SSR1




SSR2



Parameters	Unit	QWR	HWR	SSR1	SSR2
β_g	-	0.047	0.12	0.30	0.51
F	MHz	81.25	162.5	325	325
Aperture	mm	40	40	50	50
QR_s	Ohm	21	42	98	112
R/Q	Ohm	468	310	246	296
V_{acc}	MV	0.9	1.3	1.9	3.6
E_{peak}/E_{acc}		5.6	5.0	4.4	3.9
B_{peak}/E_{acc}		9.3	8.2	6.3	7.2
$Q_{calc}/10^9$	-	1.7	4.1	9.2	10.5
Temp.	K	4.5	2	2	2

EM design optimization: Parameters sweeping


➤CAVITY Manufacturing Process



MATERIAL INSPECTION



DEEP DRAWING



MACHINING



3D SCAN (CMM)



BCP



EBW

SSR Cavity Prototyping

➤ CAVITY PARTS – Material: Nb



SPOKE



END COVER




OUTER CYLINDER



BEAM TUBE 1



BEAM TUBE 2



VACUUM TUBE

Cavity Prototyping - EBW Test



Prototyping SC Cavity


QWR Final EBW



HWR Clamp-up Test



SSR1 Clamp-up Test



SSR2 Clamp-up Test






Final welding will be done in June by Vitzrotech and SFA.

Vertical tests will be performed in 2014.


WEPRI035 (IPAC2014)

RF Coupler

- Prototyping: SNU (Aug. 2013~Feb. 2014)
 - Performance test in progress
- Frequency: 325 MHz
- Nominal Power: 14.5 kW




- Prototyping: IHEP (Mar. 2014~Dec. 2014)
- Frequency: 162.5 MHz
- Nominal Power: 3.7 kW




RF power :4kW


Window and Inner conductor with air cooling is available.




QWR Cryomodule




HWR#1 Cryomodule




HWR#2 Cryomodule



SSR#1 Cryomodule



SSR#2 Cryomodule





Module	Thermal load (4.5K equivalent, W) Without margin		
	Static	Dynamic	Total
QWR	227	532	760
HWR1	389	557	945
HWR2	682	1,459	2,141
SSR1)	475	1,014	1,489
SSR2	790	5,009	5,800
Total	2,563	8,572	11,135

tolerance	unit
X	$\pm 0.25\text{mm}$
Y	$\pm 0.25\text{mm}$
Z	$\pm 0.5\text{mm}$
Pitch	$\pm 0.1^\circ$
Yaw	$\pm 0.1^\circ$
Roll	$\pm 0.1^\circ$

WEPRI035, WEPRI036 (IPAC14)

QWR Cryomodule



4K He line

Material : STS316L
Pipe inlet Size : 32A Sch5S
Pipe outlet Size : 50A Sch5S
Gasket : Helicoflex

40K He line

Material : Cu
Pipe inlet Size : 3/8" Tube
Gasket : VCR fitting

Vacuum line

Material : STS316L
Pipe inlet Size : 65A Sch5S
Gasket : Helicoflex


Safety line

Material : STS316L
Pipe inlet Size : 65A Sch5S
Gasket : Helicoflex

Stress (Condition : Vacuum)

A: Static Structural
Equivalent Stress
Type: Equivalent (von-Mises) Stress
Unit: MPa
Time: 1


78.14 Max
69.458
60.776
52.094
43.411
34.729
26.047
17.365
8.6823
2.8728e-6 Min




Displacement (Condition : Vacuum)

A: Static Structural
Total Deformation
Type: Total Deformation
Unit: mm
Time: 1

0.80769 Max
0.71795
0.6282
0.53846
0.44872
0.35897
0.26923
0.17949
0.089743
0 Min







(b) Rotating C stripper

Charge state evolution(top left), charge state distribution(top right), energy loss(bottom left) and 5Q+ populations for Uranium with C foil





Design of Li Charge Stripper




Schematic drawing of Li stripper



Cold trap of Li purifier




Charge state evolution(top left), charge state distribution(top right), energy loss(bottom left) and 5Q+ populations for Uranium with Li




Design of EM pump

Cryogenic System


- Total HL = SCL1,2,3 + Distribution + IF + Beam Loss + ZDS
= 11.0 + 1.0 + 0.5 + 0.2 + 0.1 = 12.8 (kW)
- Cryoplant Capacity : **19.2 kW** (with 50% margin) → "18 kW Plant"




Helium Distribution System P&ID



RF system




Control system






2 kW SSPA Unit Test





7 kW Full Power Test




LLRF+SSPA integration test

Setup




- ✓ With feedback control
- ✓ LLRF+SSPA
- ✓ 3 h CW operation

Long Term Test Result




@ 3 kW	Max
Power	0.06%
Phase	0.02°

SRF Test Facility



- It will be ready for operation in 2015.
- 2 vertical test stands
- 3 cryomodule test benches
- 1 buffered chemical processing
- 2 high pressure rinsing
- 1 high temperature furnace
- 1 ultrasonic clean
- Cryogenic system



- Superconducting linac has been designed to meet the requirement of science goals and various users.
- Superconducting cavities have been designed for four different types, and their prototyping is done and under cold test.
- Cryomodules have been designed, and their prototyping is under way.
- Budget of thermal load and requirement of cryogenic system are documented.
- RF power sources (SSPA) are prototyped and being tested.
- SRF test facility will be completed in mid 2015.



Thank you !
감사합니다 !

