

Status of a Project X Front-End Test Facility


2011 Particle Accelerator Conference

**Jim Steimel, Bob Webber, Robyn Madrak, Dave Wildman,
Ralph Pasquinelli, Elmie Evans-Peoples**

March 30, 2011



- Novel High Intensity Neutrino Source (HINS) design to increase neutrino flux out of Fermilab Main Injector
- Prototyping began in 2005 under HINS program




- Beam Specification: 25 mA peak, 1 ms pulse length, 10 Hz rep-rate
- All RF components driven by a single 325 MHz RF klystron
- Superconducting RF transition energy at 10 MeV
- Low beta acceleration by 325 MHz superconducting spoke cavities



Cavity Test Enclosure

Klystron & RF Distribution



Beam Line Enclosure

2.5 MW Klystron and RF Distribution




- 325 MHz Toshiba klystron
- Capable of 3 ms pulse at 2.5 Hz or 1 ms pulse at 10 Hz
- Series of waveguide switches can route power to beam line or cavity test cave





- Starts with ion source and 325 MHz RFQ
- The rest of the beam line is focusing and instrumentation




- Used to test the beam quality out of the 2.5 MeV RFQ
- Enclosure is rated for 10 MeV, 25 mA protons at 1% duty cycle




Parameter	Specified	Measured
Beam Energy	2.5 MeV	2.5 MeV
Pulse Width/Rep Rate	3 ms/ 2.5 Hz	100 μ s/1 Hz
Output Current	20 mA	4 mA
Transverse Emittance (axi-symmetric beam)	0.26π mm/mR	???
Longitudinal Emittance	150π keV*deg (rms)	???

- RFQ output energy confirmed last year.
- Initial problems with cooling water leaks into vacuum system limited average power.
- RFQ water lines have been modified and repaired.
- Expect to re-commission beam line next week.
- Output current and emittance measurements affected by ion source issues.



- More than half of proton source current due to H^{2+} and H^{3+} .
- Higher order species saturates wire signal making emittance measurements difficult.
- Plans to replace proton source with H^- source in June 2011.

Cavity Test Cave with Cryostat




- Successful test of 325 MHz SC spoke resonator pulsed to ~ 37 MV/m by R. Madrak.






- Extended beam line contains four copper spoke resonators and two buncher cavities
- Increases beam energy from 2.5 MeV to 3 MeV
- Main purpose is to test concept of single RF source for multiple cavities
- Expect to start commissioning in June 2011



RF Distribution with Vector Modulators



- RF Distribution for six cavity test is in place.
- Large boxes are variable delay lines. Vector modulators are in front of lights.




- Test of VM with 6 kW RF.
- Purple trace is amplitude modulated RF..







- Incorporates many HINS specifications
- CW front end makes most HINS components incompatible
- Facility still useful for testing Project X components





- A beam chopper is necessary to deliver proper bunch patterns to the Project X experiment. Chopper must be capable of extinguishing an arbitrary pattern of single bunches from the bunch train.
- Kickers require 250V voltage swing with <1.2 ns rise times. Beam dump must handle ~ 12 kW of beam power.
- Verification of operation is an important step in proving the feasibility of Project X.





- Project X transition to superconducting RF at 2.5 MeV
- Lowest transition energy for any high intensity hadron accelerator
- Figure shows spoke resonator cryomodule design used for low beta section (SSR0)
- Spoke resonators have never been tested with beam
- Beam enclosure needs 2K cryo distribution upgrade.



Summary



- The facility will be available for any Project X component and instrument testing with beam parameters listed below.
- The facility will also be available for testing low-beta spoke resonators in test cryostats.

Beam Energy	2.5 or 3 MeV
Bunch Spacing	325 MHz
Pulse Width/Rep Rate	Up to 1ms at 10Hz or 3ms at 2.5Hz
Beam Species	H ⁺ or H ⁻
Ion Source Energy	50 keV
Available RF Power	2.5 MW (peak)