

Commissioning and Operation of the 1.5 GeV Harmonic Double-Sided Microtron at Mainz University

Andreas Jankowiak
Institut für Kernphysik
Johannes Gutenberg - Universität Mainz

23.06.2008

EPAC⁰⁸ Genoa, Italy
magazzini del cotone

11th European Particle Accelerator Conference

June 23 - 27, 2008




- **Short Introduction: The Mainz Microtron MAMI**
- **Harmonic Double-Sided Microtron (HDSM) Design**
dipoles with field gradient, harmonic rf-system
- **Construction**
dipole field correction, 4.90GHz rf-systems
- **Commissioning**
first beam, first beam measurements, first experiment
- **Operation**
beam parameters, operation statistic
- **Future Prospects**

The Mainz Microtron MAMI B

cascade of three race track microtrons


10.08.1990: first 855MeV beam MAMI B

6000 - 7000h operation / year
for nuclear physics experiments




- 883MeV, $\sigma_E = 0.013\text{MeV}$ (0.001%)
- max. $103\mu\text{A}$ cw current
- $\varepsilon_h = 8\text{ nm rad}$, $\varepsilon_v = 0.5\text{ nm rad}$
(allows for beam foci of $\sim\mu\text{m}$)
- Halo: $< 10^{-5}$ at $r > 5 \cdot \sigma_r$

The Mainz Microtron MAMI B, RTM3



The Mainz Microtron **MAMI C**



1999: new Collaborative Research Center
Decision to add a fourth stage

(in existing buildings)


- goal: $\sim 1500 \text{ MeV}$
- max. $100 \mu\text{A}$ cw current
- same beam quality as MAMI B
- make use of Institutes expertise
(nc-cw linac structures, magnet design)

A fourth race track microtron ?

$E=855\text{MeV}$

$E=1500\text{MeV}$

($B = 1.28\text{ T} = \text{const.}$)




A fourth race track microtron ?

$E=855\text{MeV}$

$E=1500\text{MeV}$

($B = 1.28\text{ T} = \text{const.}$)



Double Sided Microtron (K.-H. Kaiser)

2000 to **our solution** 2000 to

Double Sided Microtron (K.-H. Kaiser)

250 t

250 t




our solution

250 t


250 t

Double Sided Microtron (K.-H. Kaiser)



43 turns, 855MeV $\rightarrow$ 1500MeV

dynamic coherence condition of a DSM:
path length increase from turn to turn must be equal to $2 \times \lambda$




$$\Delta E = \lambda \cdot \frac{e \cdot c \cdot B}{\pi - 2}$$

$$\left\{ \frac{2\pi}{4} (R_{i+1} - R_i) - (R_{i+1} - R_i) \right\} \cdot 4 = 2 \cdot (\pi - 2) \cdot \Delta R = 2 \cdot \lambda$$

phase advance / turn
must be $2 \times 2\pi$ in a DSM !

e.g.: $B = 1.28 \text{ T}$, $\lambda = 0.1224 \text{ m}$ (2.45 GHz) $\Rightarrow \Delta E = 41.1 \text{ MeV}$
(with nc cw-sections: linac $\sim 45 \text{ m}$)

dynamic coherence condition of a DSM:
path length increase from turn to turn must be equal to $2 \times \lambda$



$$\Delta E = \lambda \cdot \frac{e \cdot c \cdot B}{\pi - 2}$$

$$\left\{ \frac{2\pi}{4} (R_{i+1} - R_i) - (R_{i+1} - R_i) \right\} \cdot 4 = 2 \cdot (\pi - 2) \cdot \Delta R = 2 \cdot \lambda$$



phase advance / turn
must be $2 \times 2\pi$ in a DSM !

e.g.: $B = 1.28 \text{ T}$, $\lambda = 0.1224 \text{ m}$ (2.45 GHz) $\Rightarrow \Delta E = 41.1 \text{ MeV}$
(with nc cw-sections: linac ~~$\sim 45 \text{ m}$~~)


Therefore here: $\lambda_{\text{DSM}} = 0.5 \cdot 0.1224 \text{ m} \Rightarrow \Delta E = 20.5 \text{ MeV}$
(linac $\sim 20 \text{ m}$)

The fundamental frequency of the DSM must be
4.90 GHz instead of 2.45 GHz !



compensation of vertical
fringe-field defocusing ?




compensation of vertical
fringe-field defocusing ?



dipole with field-gradient




HDSM Design, consequences of the field gradient




With increasing energy the beam intrudes deeper and deeper into the 90° dipoles and experiences, compared to a homogenous dipole, turn by turn a relatively decreasing field-integral, which requires less energy gain per turn to fulfil the dynamic coherence condition.

HDSM Design, consequences of the field gradient




HDSM Design, consequences of the field gradient



stop band when certain phasing error between linac 1 and linac 2


Scheme of longitudinal bunch positions in a DSM

(remember: sub-harmonic injection with 2.45GHz into a 4.90GHz rf-system)



2 Linacs, operating at $\nu_1 = 4.90\text{GHz}$ resp. $\nu_2 = 2.45\text{GHz}$

Harmonic Double Sided Microtron (HDSM)




— — — instable region of longitudinal motion for 4.90GHz wave

Harmonic-operation (highest longitudinal beam stability)

DSM, 2 x 4.90GHz linac


longitudinal phase-space DSM
linacs $\Delta\phi=3^\circ$ error (relative to 4.90GHz)



Harmonic-operation (highest longitudinal beam stability)


DSM, 2 x 4.90GHz linac

longitudinal phase-space DSM
linacs $\Delta\phi=3^\circ$ error (relative to 4.90GHz)




HDSM, 4.90GHz + 2.45GHz Linac

longitudinal phase-space HDSM
linacs $\Delta\phi=5^\circ$ error (relative to 4.90GHz)



The Harmonic Double Sided Microtron (HDSM)



Best approximation to the inherent stable and reliable RTM principle

Construction: dipoles with field gradient



Design and construction drawings by KPH

Transport and installation of all four magnets finished in 2002

measurement of the magnetic field of all 4 magnets to get the data for the construction of surface correction coils

Magnet as it is: $\Delta B/B \sim 10^{-3}$
(in the central area: $\sim 10^{-4}$, excellent manufacturing quality)

required is: $\Delta B/B \sim 10^{-4}$


measurements finished: 09/2003

correction coils ready and checked, magnets finally assembled: 03/2006






Construction: field correction

HDSM dipole 03, field map
(normalized to ideal field gradient, $B_{\max}=1.539\text{T}$ for 1508MeV)




Construction: field correction

HDSM dipole 03, field map
(normalized to ideal field gradient, $B_{\max}=1.539\text{T}$ for 1508MeV)



Construction: 4.90GHz linac

8 linac sections ("in house" development, 35ACs, 81M Ω /m)
9.0MV: 117kW rf-power + 38kW beam loading (@100 μ A)




klystrons (4 $\times$ TH2166, 50kw cw)

- successful section prototype test: 07/2003
- last section delivered: 02/2006
- first module (No. 3) tested: 08/2006
- ready installed, under vacuum, power tested: 21.11.2006
- final phasing: 06.12.2006


4.90GHz/50kW cw klystron TH2166:



Construction: 4.90GHz linac



Construction: 180°-bending system




For both 180°-bending systems:
 $2 \times 2 \times 43 = 192$ vacuum tubes
 $2 \times 2 \times 2 \times 43 = 384$ corrector magnets

EPAC08, Genua - Italy

Commissioning: November 2006, first full turn

(4.90GHz linac not ready, no acceleration)

After one full turn without acceleration
the beam enters for a second time
Dip01 and is again bent by 90°.




Field in Dip03+04 reduced by $\sim 9\text{MeV}/855\text{MeV} = 1.05\%$

Commissioning: November 2006, first full turn

(4.90GHz linac not ready, no acceleration)

After one full turn without acceleration
the beam enters for a second time
Dip01 and is again bent by 90°.



Field in Dip03+04 reduced by $\sim 9\text{MeV}/855\text{MeV} = 1.05\%$


Commissioning: 19. December 2006, 43 turns

43 turns: 19³¹h (after ~8h)

diagnostic pulse mode:

100 μ A peak, 12ns, max. 10kHz = 12nA average

855.3MeV beam
from RTM3



(extraction beamline still not ready)

Commissioning: 19. December 2006, 43 turns


43 turns: 19³¹h (after ~8h)

diagnostic pulse mode:

100 μ A peak, 12ns, max. 10kHz = 12nA average

855.3MeV beam
from RTM3

synchrotron radiation
monitor



(extraction beamline still not ready)

19.12.2006, beam not well matched, beam losses observed

turn 43

turn 1

DIP 4 20


20.12.2006, beam well matched, no beam losses observable
(with the available diagnostics)

turn 43

turn 1

DIP 4 20

Commissioning: position and phase measurement




signals of low-Q rf-monitors of both HDSM-linacs


- 4.906Hz-linac

- 2.456Hz-linac

Commissioning, optimisation of corrector magnets




Commissioning, optimisation of corrector magnets




Commissioning: optimisation of corrector magnets

return path system Dip1+2, horizontal




(design max. values: horizontal 3mrad, vertical 2mrad @ 1.5GeV)


Commissioning: January-February 2007




Commissioning: January-February 2007



08.01.2007 - 24.01.2007: 5 days of beam tests
Beam on diagnostic beam dump (first extracted beam) !




Commissioning: January-February 2007




08.01.2007 - 24.01.2007: 5 days of beam tests
Beam on diagnostic beam dump (first extracted beam) !

06.02.2007 - 08.02.2007: 2 days of beam tests
Beam guided through extraction to SFTFLUMO16



Commissioning: January-February 2007




08.01.2007 - 24.01.2007: 5 days of beam tests
Beam on diagnostic beam dump (first extracted beam) !

06.02.2007 - 08.02.2007: 2 days of beam tests
Beam guided through extraction to SFTFLUMO16

13.02.2007 - 23.02.2007: 7 days of beam tests
First beam on A1 dump; first "high power" operation ($10\mu\text{A}$);
first polarized beam ($\sim 80\%$)

Operation: first user run

23.02.2007 - 05.03.2007 user operation
1.508 GeV, 10 μ A,
polarised beam ~83%



Fr., 23.02.2007, 12.00


till

Mo., 05.03.2007, 6.00

**Operation: all experimental stations commissioned with beam
within only 1½ months**

**A4 - Parity violating
electron scattering**
30.03.2007: first beam
02.04.2007: 15 μ A

A2 - Tagged photon beams
29.03.2007: first beam



A1 - Three spectrometer set-up
13.02.2007: first beam

Operation: all experimental stations commissioned with beam within only $1\frac{1}{2}$ months

A4 - Parity violating
electron scattering
30.03.2007: first beam
02.04.2007: $15\mu\text{A}$


A2 - Tagged photon beams
29.03.2007: first beam

October 2007:
high power beam test

$100\mu\text{A}@1.508\text{GeV} = 150\text{kW}$ beam power


From beam loss monitor system one can estimate:
beam losses well below 10^{-5}
very "clean" operation, as it used to be with MAMI B

A1 - Three spectrometer set-up
13.02.2007: first beam




Operation: beam time statistic

10.08.1990 - 02.05.2008: 100.000h of operation with MAMI



Operation: longitudinal beam dynamic

evaluation of measured phases



result of fit

4.90GHz-Linac (linac I): $+9.2^\circ / 8.60\text{MV}$ ($\Delta E_{\text{tot}}=343\text{MeV}$) (measured: $+9.1^\circ$)


2.45GHz-Linac (linac II): $-30.6^\circ / 9.46\text{MV}$ ($\Delta E_{\text{tot}}=310\text{MeV}$) (measured: -31.5°)

$E_{\text{INJ}}=855.243\text{MeV}$ ($\Delta E_{\text{inj}}=80\text{keV}$), $E_{\text{out}}=1508.8\text{MeV}$

Operation: longitudinal beam dynamic

evaluation of measured phases

$\Phi_{2.45\text{GHz}} - 3.3^\circ$ (first beam losses detectable)



result of fit


4.90GHz-Linac (linac I): $+9.2^\circ$ / 8.60MV (measured: $+9.1^\circ$)

2.45GHz-Linac (linac II): -34.5° / 9.46MV (measured: -34.8°)

$E_{\text{INJ}}=855.243\text{MeV}$, $E_{\text{out}}=1509.2\text{MeV}$

Operation: emittance measurement

making use of return path synchrotron radiation monitor



5.32mm

extracted beam

9.20mm

well known optical distances between consecutive turns (decreasing from turn1 → turn42)

turn42


turn1

CCD camera (640pix × 480pix), min. shutter time 10μs
pixel size: $h=8.3\mu\text{m}$ / $v=8.3\mu\text{m}$

Operation: emittance measurement

10 μ A cw, 10 μ s shutter time (30.05.2007)


(current and shutter adjusted for no saturation)



$$\sigma_h = 2.215 \text{ pix} = 0.301 \text{ mm},$$
$$\beta_h \sim 7.4 \text{ m}$$

$$\rightarrow \varepsilon_h = 12 \text{ nmrad}$$

(influence of finite energy width of only 80 keV in dispersive section is negligible)



$$\sigma_v = 2.05 \text{ pix} = 0.279 \text{ mm},$$
$$\beta_v \sim 40.3 \text{ m}$$

$$\rightarrow \varepsilon_v = 1.9 \text{ nmrad}$$

(measurement limited due to optical resolution of the system)

Simulations predict:

$$\varepsilon_h = 9 \text{ nmrad} \text{ and } \varepsilon_v = 0.4 \text{ nmrad}$$

Future prospects:

- making efficient use of return path synchrotron light monitor:
emittance measurements, automated matching procedures
- phase cavities for relative energy measurements:
energy stabilisation up to 10^{-6} for parity violating electron scattering at 1.508 GeV
- measurements of absolute beam energy (10^{-4}):
making use of well known dipole fields
- end energy increase:
first test $E_{inj}=883\text{MeV} \rightarrow E_{out}=1557.3\text{MeV}$
then higher fields, new correction plates, rf-systems
testing the limits of our design

Conclusion:

- We have designed, built and commissioned the first Harmonic Double Sided Microtron
- A HD SM allows for two times higher maximum energy for the same iron weight compared to an RTM
- The HD SM operates very reliable and stable. It delivers a high power (150kW), low emittance beam with very small energy spread and $> 80\%$ polarization
→ best continuation of the outstanding RTM principle