

MESA @ bERLinPro

Joint Forces in Pursue of ERL Magnificence

Speaker: Sebastian Thomas

Workshop on Energy Recovery Linacs in Berlin 2019

HIM HELMHOLTZ
Helmholtz-Institut Mainz




Cluster of Excellence
PRISMA⁺

Precision Physics, Fundamental Interactions
and Structure of Matter

- Introduction
 - Mainz Energy-Recovery Superconducting Accelerator MESA
 - Berlin Energy Recovery Linac Project bERLinPro
 - MESA @ bERLinPro
- The MESA Cryomodule
- Planning the Field Campaign
- Outlook

- Modes of operation:
 - External (polarized, up to 150 μA , 155 MeV)
 - ERL (unpol., up to 10 mA, 105 MeV)
- Experiments:
 - P2 (Weinberg angle Ω_W), BDX (dark photons)
 - MAGIX (Astrophysical S-Factor)
- Structures:
 - Source “Steam” (200 keV, pol.)
 - Manipulation beamline “MELBA”
 - NC Injector “MAMBO” (5 MeV)
 - Two SRF Cryomodules (25 MeV each)




	Basic Parameter
max. beam energy	50 MeV
max. current	100 mA (77 pC/bunch)
normalized emittance	1 μm (0.5 μm)
bunch length (straight)	2 ps or smaller (100 fs)
rep. rate	1.3 GHz
losses	$< 10^{-5}$

- Project started 2011, fully funded
- Building ready 2017
- First electrons 2018
- Recirculation beam line 2019/2020

Test and diagnostic line

(5mA@10MeV dump,
energy & slice diag.)



SRF gun

(1.4 cell srf cavities
1.5-2.3 MeV, single solenoid)

Modified Cornell booster

(3 x 2 cell srf cavities
4.5 MeV)

Linac module

(3 x 7 cell srf cavities
44 MeV)

Beam dump


(6.5 MeV, 100 mA
= 650 kW)

MESA @ bERLinPro



bERLinPro: existing hall, injector and recirculation beam line

but no linac cryomodule

MESA: existing cryomodule
but no hall, recirculation, ...





MESA Cryomodule
(modified ELBE type)



Position to integrate
MESA Linac Module
(5m free space
available)


MESA Cryomodule



- ELBE Type Cryomodules with modifications:
 - Added XFEL piezo tuners
 - Modified HOM dampers and feedthrough
- 9-cell TESLA Nb Cavities, 1.3 GHz, $Q = 1.25 \times 10^{10}$ @ 12.5 MV/m
- Cavities tested at DESY vertical test stand
- Modules are currently tested at Mainz
- First module passed SAT



S. Thomas, MESA, 17.09.19



Cryogenics




Dewar
(phase separation, LHe storage)

MCTL
(LHe, GHe, LN2)


Valve Box
(level, pressure regulation)

Cryomodule
(2 XFEL Cavities @ 12.5 MV/m)


LHe/LN2 supply box
(JT valve & heat exchanger)



Cryomodule Test Site





- Measured heat load of the module 1 at 2 K
 - $P_{static} = 9.0 \text{ W}$
 - $P_{dyn, 12.5 \text{ MV/m}} \leq 15.7 \text{ W}$
- Integration into the bERLinPro Cryosystem needs replacing of the Helium supply box on top of the module
- Helium pressure in bERLinPro higher than MESA, safety valves need to be redesigned





Vacuum


- The module will be delivered to Berlin evacuated and being constantly pumped
- First, the module will be tested still connected to the MESA vacuum system
- Then, the connection to the bERLinPro system will be established
 - An adapter unit (DN100 to DN40) is being designed by a bachelor student
 - Assembly will happen under clean room conditions




- Low energy spread demands
 - High amplitude stability $< 0.01 \%$
 - High phase stability $< 0.01 \%$
- PLL used for SAT, μ TCA based LLRF will take over operation in accelerator
- LLRF system is tested parasitically in module test at Mainz



→ LLRF + PLL nested control loop



→ LLRF control loop



PLL: Frequency modulation
 → Resonance frequency control loop
LLRF: Amplitude modulation
 → Amplitude & Phase control loop


After all connections are established, the module will be cooled down and the first measurements will be taken:

- Spectra of Microphonics and HOMs at the new location
- First beam operations:
 - One pass acceleration
 - Cavity behavior in transient beam loading
 - Differently pulsed beams will be used
 - Control accuracy of the LLRF will be tested

After that was successfully completed, we will start with ERL operations:



- The excitation and damping of HOMs will be measured
- Heating of the HOM feedthroughs will be investigated
- BBU limits will be probed

Further, beam diagnostics will be integrated into the LLRF system of HZB to establish optimal timing for effective ERL operations.



Picture: T. Stengler

Outlook



Thank you!