

Initial Experiences With Beam Diagnostics During Sirius Commissioning



Brazilian Synchrotron
Light Laboratory

Henrique de O. Caiafa Duarte

Beam Diagnostics Group (DIGS)
on behalf of the LNLS/Sirius Team
Talk at IBIC 2020 (MOA002)
September 14, 2020

Outline

- Sirius Timeline
- Introduction
- Diagnostics Components Summary
- Fluorescent Screens (Flags)
- Current Monitors
- Beam Scrapers
- Tune Measurement System
- BbB FB System
- BPM, Stability and Measurements
- Final Comments




Sirius Timeline (2012-2019)


2012		- start of MBA lattice design after first MAC meeting
2015		- start of building construction
2016		- start of components production by Brazilian industry
2018	April	- 150 MeV Linac from SINAP commissioned
	May	- start of booster installation
	June	- start of storage ring installation
2019	08-Mar	- first turn in the booster @ 150 MeV
	16-Oct	- first beam energy ramp to 3 GeV
	22-Nov	- first turn in storage ring with on-axis injection
	06-Dec	- hundreds of turns without RF
	14-Dec	- first stored beam with on-axis injection, 30 uA
	16-Dec	- first light from superbend BC at Mogno beamline (20/40/68 keV Zoom Tomography)
	16-Dec	- first X-ray microtomography experimental result from Mogno

Sirius Timeline (2020)


2020	20-Feb	- first beam accumulation with non-linear kicker (NLK), 10 mA
	16-Mar	- shut-down to install scrapers. They are located in the injection straight
	23-Mar	- commissioning interrupted due to covid-19 pandemic
	23-Apr	- restart of beam tests in accelerators with signs of physical obstruction in the SR
	29-Apr	- horizontal scraper has been removed
	01-May	- beam accumulation with NLK recovered
	18-May	- 1st planar undulator instalation (Manacá beamline: 5–20 keV Serial Micro and nano MX)
	29-May	- 2nd planar undulator instalation (Cateretê beamline: 3–15 keV CDI and XPCS)
	06-Jun	- start of Manacá beamline comissioning
	01-Jul	- vertical scraper removed
	03-Jul	- beam for users at 10 mA
	11-Jul	- important milestone of Manacá beamline: first Sars-Cov-2 image →
	31-Aug	- beam for users at 20 mA with longitudinal bunch-by-bunch feedback
	18-Sep	- 3rd planar undulator instalation (EMA beamline: 3–35 keV extreme conditions)
	18-Sep	- 4th PU instalation (Carnaúba beamline: 2–15 keV Nano-XRD/XRF and Cryo-Ptychography)



Main Parameters





Storage Ring Parameters	
e-Beam energy	3.0 GeV
Circumference	518.4 m
Lattice	20 x 5BA, 5-fold symmetry
Hor. emittance (bare lattice)	0.25 nm.rad
Ver. emittance (with undulators)	0.15 nm.rad
Betatron tunes (H/V)	49.11 / 14.17
Natural chrom. (H/V)	-119.0 / -81.2
Energy spread (rms)	0.85×10^{-3}
Energy loss/turn (dipoles)	473 keV
Damping times (H/V/L) [ms]	16.9 / 22.0 / 12.9
Nominal beam current (top up)	350 mA



Booster Parameters	
Circumference	496.8 m
Emittance @ 3 GeV	3.5 nm.rad
Lattice	50 FODO
Cycling frequency	2 Hz

liu@lnls.br

Tunnel



Diagnostics Components Summary

Component	LINAC	LTB	BTS
FCT		1	1
ICT	2	2	2
Screen (Beam Flag)	5	6	6
Horizontal Slit		1	
Vertical Slit		1	
Stripline BPM	3	6	5
Beam Loss Monitor		tbd	tbd


Component	Qt per Beamline
X-BPM	2 (position+angle meas.)

sergio@lnls.br

Component	Booster	Storage Ring
DCCT	1	2
Screen (Beam Flag)	3	
Button BPM	50	160
Front-End Photon BPM		80
Filling Pattern Monitor		1
Horizontal scraper		1 pair
Vertical scraper		1 pair
Tune shaker	1	2
Tune pick-up	1	2
Bunch-by-Bunch kicker		3
Bunch-by-Bunch BPM		1
X-ray port		1
Visible light port	1	1
Streak camera		1
Beam Loss Monitor	4	
Gas Bremsstrahlung Monitor		100

Diagnostics Component: X-Ray Port

- Use of a toroidal mirror (Mo/B₄C, 3.07 nm/bilayer, 140 bilayers) to focus 11 keV X-ray beam from B1 dipole;
- Source-mirror length = mirror-focal point length = 17 m
- Image: YAG-Ce screen + CCD camera **or** 2x Si222 crystals (36x magnification) + Medipix detector




- Expected measurement uncertainty < 5%
- Mirror chamber built and leak-tight
- Mirror is under optical measurements

Component	Booster	Storage Ring
<i>DCCT</i>	<i>1</i>	<i>2</i>
<i>Screen (Beam Flag)</i>	<i>3</i>	
<i>Button BPM</i>	<i>50</i>	<i>160</i>
<i>Front-End Photon BPM</i>		<i>80</i>
<i>Filling Pattern Monitor</i>		<i>1</i>
<i>Horizontal scraper</i>		<i>1 pair</i>
<i>Vertical scraper</i>		<i>1 pair</i>
<i>Tune shaker</i>	<i>1</i>	<i>2</i>
<i>Tune pick-up</i>	<i>1</i>	<i>2</i>
<i>Bunch-by-Bunch kicker</i>		<i>3</i>
<i>Bunch-by-Bunch BPM</i>		<i>1</i>
X-ray port		<i>1</i>
Visible light port	<i>1</i>	<i>1</i>
Streak camera		<i>1</i>
Beam Loss Monitor	<i>4</i>	
Gas Bremsstrahlung Monitor		<i>100</i>

paulo.tarso@lnls.br; rubens.castro@lnls.br

Diagnostics Component: Visible Light Port

- Booster VL monitor:
 - Mirror + CMOS Camera



- For the **Storage Ring**, a VL extraction is being analyzed from the B2 dipole to feed a streak camera
- Hamamatsu C5680 streak camera from LNLS old storage ring operating at 119 MHz was modified to 125 MHz operation rate.

Component	Booster	Storage Ring
<i>DCCT</i>	<i>1</i>	<i>2</i>
<i>Screen (Beam Flag)</i>	<i>3</i>	
<i>Button BPM</i>	<i>50</i>	<i>160</i>
<i>Front-End Photon BPM</i>		<i>80</i>
<i>Filling Pattern Monitor</i>		<i>1</i>
<i>Horizontal scraper</i>		<i>1 pair</i>
<i>Vertical scraper</i>		<i>1 pair</i>
<i>Tune shaker</i>	<i>1</i>	<i>2</i>
<i>Tune pick-up</i>	<i>1</i>	<i>2</i>
<i>Bunch-by-Bunch kicker</i>		<i>3</i>
<i>Bunch-by-Bunch BPM</i>		<i>1</i>
X-ray port		<i>1</i>
Visible light port	1	1
Streak camera		1
Beam Loss Monitor	4	
Gas Bremsstrahlung Monitor		100

andrei.pereira@lnls.br

Diagnostics Component: BLM

Component	LINAC	LTB	BTS
<i>FCT</i>		1	1
<i>ICT</i>	2	2	2
<i>Screen (Beam Flag)</i>	5	6	6
Horizontal Slit		1	
Vertical Slit		1	
Stripline BPM	3	6	5
Beam Loss Monitor		tbd	tbd


Component	Booster	Storage Ring
<i>DCCT</i>	1	2
<i>Beam Flag</i>	3	
<i>Button BPM</i>	50	160
<i>Front-End Photon BPM</i>		80
<i>Filling Pattern Monitor</i>		1
<i>Horizontal scraper</i>		1 pair
<i>Vertical scraper</i>		1 pair
<i>Tune shaker</i>	1	2
<i>Tune pick-up</i>	1	2
<i>Bunch-by-Bunch kicker</i>		3
<i>Bunch-by-Bunch BPM</i>		1
X-ray port		1
Visible light port	1	1
Streak camera		1
Beam Loss Monitor	4	
Gas Bremsstrahlung Monitor		100

- 25 BLM units from Bergoz Instrumentation
- 4 units have been used in the booster so far
 - Installed in the injection sector



sergio@lnls.br

Diagnostics Components Summary: Gas Bremsstrahlung Monitor





Component	Booster	Storage Ring
<i>DCCT</i>	1	2
<i>Beam Flag</i>	3	
<i>Button BPM</i>	50	160
<i>Front-End Photon BPM</i>		80
<i>Filling Pattern Monitor</i>		1
<i>Horizontal scraper</i>		1 pair
<i>Vertical scraper</i>		1 pair
<i>Tune shaker</i>	1	2
<i>Tune pick-up</i>	1	2
<i>Bunch-by-Bunch kicker</i>		3
<i>Bunch-by-Bunch BPM</i>		1
X-ray port		1
Visible light port	1	1
Streak camera		1
Beam Loss Monitor	4	
Gas Bremsstrahlung Monitor		100

fernando.bacchim@lnls.br
carlos.scorzato@lnls.br

Screens: LINAC, Booster and TLs



- Each screen is attached to a stripline BPM (except LINAC OTR ones)
- Screens: Al₂O₃ (calibration) and YAG:Ce
- Linear Stage + Encoder: Huber 5101.20 X1
- Stepper motor: Vexta PK-266-02B
- CMOS Camera: Basler acA1300-75gm
- Controller: Galil DMC-30017





Henrique de O. Caiafa Duarte

Screens: Post-septa

- Monitors the injected beam
- Common chamber with the storage ring
- Same components of the regular screens



stored beam
injected beam



Henrique de O. Caiata Duarte


Current and Charge Monitors

■ ICTs: injection efficiency

▲ FCTs: TLs' bunch train temporal distribution

● DCCTs: booster and storage ring average current


- Bergoz sensors+BCM electronics;
- Keithley DMM7510 7 1/2-digit multimeter in:
 - Precision mode for DCCTs signals;
 - Fast mode for ICT -> BCM signals.



andrei.pereira@lnls.br

Injection Efficiency


- Typical injection efficiency during operations:




- During machine studies, efficiency usually reaches ~90% mean, ~10% std.
- EMI from septa (amplitude beating and curve slope) impedes reliable processing from the BCM electronics
- ICTs signals are currently read and processed via oscilloscopes

Beam Scrapers

- Design minimizes impedance using angular motion. A linear-to-angular motion transmission is used.
 - Components used: Vexta PK-223PB stepper motor, a Huber 5101.07 X1 linear translation stage and the same rotary encoder as the beam flags
- Main design difficulties
 - Indirect blade position feedback.
 - Movement mapped by 3D measurements, but maintenance of parts require recalibration.
- Main commissioning issues
 - After installation and baking, the linear stages of the horizontal scraper were found to be offset, not allowing one blade to fully open (~ 0.9 mm after adjustments).
 - Both horizontal and vertical scrapers were removed from the ring for inspection.
 - The weaknesses are being reinvestigated with endurance tests.
 - The opposite blade stuck after the first 2 days of testing, due to electrical contact spring partially slipping out of its housing.




Linear Motion




Angular Motion

rafael.seraphim@lnls.br
andrei.pereira@lnls.br


Beam Scrapers



Tune Measurement System




Tune Measurement: Storage Ring






Longitudinal CBMI at Manacá Beamline

23 mA



Position [px / mm]		Size [px / mm]	
X =	391 / -2.487	X =	28 / 0.287
Y =	740 / -2.294	Y =	26 / 0.268


25 mA



Position [px / mm]		Size [px / mm]	
X =	383 / -2.570	X =	41 / 0.418
Y =	732 / -2.216	Y =	48 / 0.488

lucas.sanfelici@lnls.br

Longitudinal CBMI + Petra 7-Cell Cavity




Cavity Temperature [°C]

Beam Avg. Current [mA]

RMS Synchrotron
Oscillations [dB]

Cavity Plunger Detune (°)



BbB FB: Longitudinal Plane Loop Closed



BbB FB: Disturbance from RF Clock Jitter


R&S FSUP 8 Signal Source Analyzer				LOCKED	
Settings		Residual Noise [T1]		Spur List	
Signal Frequency:	499.995822 MHz	Int PHN (1.0 k.. 1.0 M)	-44.4 dBc	25.161 kHz	-62.22 dBc
Signal Level:	-3.27 dBm	Residual PM	0.489 °	75.484 kHz	-72.61 dBc
Cross Corr Mode	Harmonic 1	Residual FM	3.947 kHz	131.570 kHz	-72.89 dBc
Internal Ref Tuned	Internal Phase Det	RMS Jitter	2.7146 ps	263.154 kHz	-75.22 dBc

Phase Noise [dBc/Hz] Marker 1 [T1] Marker 2 [T1] Marker 3 [T1] Marker 4 [T1]
 RF Atten 5 dB 75.68359 kHz 263.67188 kHz 341.79688 kHz 678.71094 kHz
 Top -20 dBc/Hz -107.83 dBc/Hz -112.17 dBc/Hz -100.14 dBc/Hz -92.84 dBc/Hz



Downsampling = 1


MARKER	SPAN (kHz)	MIN	MAX	MARKER	FREQ
1	2.00	2.20	MAX	-6.5 dB	2.11 kHz
2	0.00	250.00	MIN	33.0 dB	103.50 kHz



Downsampling = 2

MARKER	SPAN (kHz)	MIN	MAX	MARKER	FREQ
1	2.00	2.20	MAX	-7.0 dB	2.11 kHz
2	0.00	250.00	MIN	29.9 dB	103.49 kHz

BPM Electronics




Timing event
receiver

Storage Ring
Electron BPM
RF digitizers

Booster
Electron BPM
RF digitizers

XBPM digital picoammeters
(I/O modules by CAENels)

BPM Rack Front View




RFFE
Modules

MicroTCA.4
crate

Ethernet
switch

RFFE
Modules



RFFE

500 MHz band-pass filtering
25 MHz bandwidth
Up to 35 dB amplification
2x2 channel switching
Open hardware

daniel.tavares@lnls.br
gustavo.bruno@lnls.br
lucas.russo@lnls.br

Open hardware designs and open source gateway
and software codes are available at:

<http://github.com/lnls-dig>
<https://www.ohwr.org/projects/afc>

A Generic MicroTCA.4 DAQ Platform


daniel.tavares@lnls.br; lucas.russo@lnls.br; gustavo.bruno@lnls.br

AMC FMC Carrier
Generic FPGA board
with 2 FMC HPC slots
and RTM-capable


Open Hardware

Usage at Sirius:

- 1) RF BPM digitizer
- 2) XBPM digitizer
- 3) MTCA.4 EVR
- 4) FOFB Controller




8 SFP RTM
8 SFP cage and
clock resources
for optical I/O
Open Hardware



FMC ADC 250 MS/s
16-bit 4-channel fast
ADCs

Open Hardware




FMC POF
5-channel plastic
optical fiber I/O

Open Hardware




FMC-4SFP+
4 SFP cage and clock
resources for optical I/O
for FOFB System

By CAENels




FMC-Pico-1M4
4-channel fast
picoammeter

By CAENels





lucas.sanfelici@lnls.br

BPM Sensor





BPM Sensor



- 160 BPMs



- All BPM parts contracted to Brazilian industry
- In-house button assembly, brazing and welding
- All BPMs have bellows on both sides and are referenced to the girders by design



rafael.seraphim@lnls.br

BPM Deformation from Unbalanced Wake Heat Load

$$I_{av} = 100 \text{ mA}, \sigma_s = 2.5 \text{ mm}$$




thiago.rocha@lnls.br
(thermomechanical analysis)


150 nm relative vertical offset: **300 nm BPM electrical center deviation** (from studies of electrical deviation). Since Sirius requires **sub-hundred nanometer stability**, sorting the buttons by similar gap size (or, close capacitance values) is required.

Button Capacitance Measurement

Capacitance measurement histogram – First batch (727 buttons) @ 2017






Capacitance measurement histogram – Second batch (538 buttons) @ 2018



BPM Offset: Button Sorting

rafael.defavari@lnls.br




Housing seat offset


Each BPM was assembled with 4 feedthroughs with:

- Similar capacitance ($< 1\%$) – hence similar gap sizes;
- Complementary housing seat and button offset – so the buttons face the same distance from BPM center


BPM Offset: Offset Correction and BBA



Electrical offsets (long cables + electronics)





BBA offsets (after offset correction)



fernando.sa@lnls.br
murilo.alves@lnls.br
liu@lnls.br

BPM: Injection Kicker EMI Filter

Implementation of a high-pass 13 taps FIR filter, cut-off frequency @ 35 MHz




daniel.tavares@lnls.br


Dynamic Aperture Fitted Measurements

- All BPM readings (TbT data) were fitted with the nominal machine model for each turn: position and angle at the kicker location extracted as result;
- Measured dynamic aperture of **-9 mm**

Kicker angle: m850urad_lococorr_newtunes




fernando.sa@lnls.br; murilo.alves@lnls.br; liu@lnls.br




Orbit Stability

- Orbit correction currently operates at 25 corrections/s
 - Attenuates thermal effects and ID phase changes only
- Machine time needed to continue studies with XBPM
- Tunnel temperature stability improvements ongoing
- Investigations and improvements are needed: interferences from mains and booster 2 Hz ramping, vibrations, "cultural noise"
- FOFB expected to come online Q2/2021



fernando.sa@lnls.br; murilo.alves@lnls.br; daniel.tavares@lnls.br; liu@lnls.br

High beta straight section BPM only



Final Comments

- The booster commissioning in parallel with storage ring installation led to an intermittent schedule
- Emittance measurements not available yet: diagnostics beamline under review
- Streak camera not installed yet
- EMI issues with charge measurements
- Beam loss: Commercial PIN diodes BLMs used for booster commissioning and in-house developed Gama detectors in the storage ring. Commercial PMT-based BLMs can be considered for upgrades/cross-checks
- Both horizontal and vertical scrapers are under test after design changes
- Orbit stability improvements are demanded
- Screens: success (but could be less expensive)
- Standardization of components has proven fruitful already: motors, cameras, digitizers (ICTs and DCCTs) etc.
- Bunch-by-bunch feedback longitudinal system running for users and improvements are ongoing

An aerial photograph of a large, circular industrial facility. The facility has a prominent, wide, silver-colored corrugated metal roof that forms a ring around a central area. Inside this central area, there are several large blue cylindrical storage tanks, a network of white pipes and walkways, and some smaller buildings. The outer ring of the facility has a lower level with large glass windows. Surrounding the facility are green lawns, parking lots with several cars, and a road with crosswalks. The overall scene is brightly lit, suggesting a sunny day.

Thank you!