





Commissioning of the European XFEL Injector



Frank Brinker, DESY
for the commissioning team



HELMHOLTZ
| ASSOCIATION





View into the injector tunnel



Stepwise commissioning during installation


In order to gain valuable experiences with the different systems at an early stage the commissioning started already end of 2013 with the gun.





After RF operation of the gun in Dec 2013 and Sept. 2014 the UV-laser installation was finished beginning 2015 :

February 10th 2015 First photo electrons from the XFEL Gun!:



1.3 GHz, 1.5 cells

$Q_0 \cong 20000$

Gradient on cathode: 50 – 60 MV/m

650 μ s pulse length , 10 Hz rep. rate

Max. average RF Power: **42 kW**


Emittance (1nC) : < 0.9 mm mrad

Cs₂Te Cathode

Screen picture of the first photo electrons at XFEL –
3mm Aperture, 20 Bunche, 10 Hz, ca. 2nC

Operations panel of the laser system (MBI, Berlin)

Here : 30 Laser pulses



Pulse energy

Laser profile before the aperture

and on the virtual cathode


The screenshot displays the operations panel for the laser system. It is divided into several sections:

- Gun Laser Status/Control:** Shows the status of various components: Power (220 V), Oscillator, Pre-amplifier, and Booster, all of which are ON. It also includes buttons for 'Power ON', 'Oscillator ON', 'Preamp ON', and 'Booster ON', along with a 'Main' button.
- Laser controls:** A table of status indicators:

<input checked="" type="checkbox"/> Power (220 V)	<input checked="" type="checkbox"/> (1) Power is on
<input checked="" type="checkbox"/> Oscillator	<input checked="" type="checkbox"/> (3) Oscillator is ok
<input checked="" type="checkbox"/> Pre-amplifier	<input checked="" type="checkbox"/> (4) Preamp is on
<input checked="" type="checkbox"/> Booster	<input checked="" type="checkbox"/> (5) Booster is on

 Below this is an 'Amplifier Status' section with green indicators for 'Preamp ON', 'Multi-pass ON', and 'Booster ON', each with 'No Warning' and 'No Error' status. A 'Reset' button is also present.
- Output power diagnostics:** A line graph showing 'Toroid 3GUN [mA]' over time from 5h to 17h on 24.2.2015. The mean value is 3.250e+04 and the standard deviation is 1.788.
- Burst diagnostics:** A graph showing pulse bursts over time, with a zoomed-in view of a burst between 796 and 810 microseconds.
- Beam profile at aperture:** Displays four beam profiles: 'Far field beam profile', 'Near field beam profile', 'Virtual cathode beam profile', and 'Near field beam profile'. The 'Virtual cathode beam profile' shows a distinct spot.
- System Overview:** A block diagram of the laser system components:
 - Oscillator (red box) feeds into PC1 (yellow box), which feeds into a PCF fiber amplifier (purple box).
 - The PCF fiber amplifier feeds into a Multi-pass Amplifier (yellow box), which feeds into Booster Amplifier I (green box).
 - Booster Amplifier I feeds into PC2 (yellow box), which feeds into Booster Amplifier II (green box).
 - Booster Amplifier II feeds into FHG (blue box), which feeds into an Attenuator (blue box).
 - The Attenuator feeds into the Aperture X/Y (grey box), which outputs 'To beamline and gun diagnostic'.
 - A Balanced X-correlator (orange box) is connected to the Oscillator and the system.
 - Heater Amplifier I and Heater Amplifier II (green boxes) are also connected to the system.
 - RPC Utility and DOOS Watchdog (blue boxes) are shown at the top of the overview.

November 2015 : complete Installation is finished with the 3rd harmonic module (INFN)





September 23 2015



November 11 2015


Installation of the XFEL cryo plant finished:



Distribution
box(BINP)


Cold compressor
box (Linde)

After technical commissioning of the modules : Injector cooldown




- December 9
 - Starting cooldown of the the injector for the first time.
 - First cooldown of AH1 module at all !
- December 14
 - Injector is at 2K
- December 15
 - Stable 2 K in the injector with cold compressors.

Accelerating 1.3 GHz module A1




- Cavities were tuned to resonance between December 16. - 18.
- December 18.
 - Rough calibration of all cavity signals
 - All loaded Q were adjusted to 4.6e6 using the automatic QI adjustment tool.
 - All feedback loops were closed and module was running with nominal amplitude.





/svn/XFEL/LLRF/SC_modules/Injector/XLLRF_inj_diag_cav.xml XFELRF/LLRF.DIAGNOSTICS/A1.I1/

Diagnostic server readouts f...	MAIN.M12.A1.I1								
	C1	C2	C3	C4	C5	C6	C7	C8	
dA/A pulse2p	0.0040	0.0053	0.0127	0.0017	0.0029	0.0060	0.0104	0.0126	%
dP pulse2p	0.2359	0.2024	0.1343	0.1609	0.1214	0.1344	0.0958	0.1849	deg
loaded Q	4.49E6	4.57E6	4.59E6	4.57E6	4.62E6	4.52E6	4.62E6	4.60E6	
Detuning	-100	-145	17	-97	-259	-91	-167	-179	Hz




Cavity phasing of A1 was achieved January 9, 2016.





$\approx 1\%$ of accelerator length
 $\approx 1\%$ of final energy
 $\approx 1\%$ of electrons/second
 but all accelerator sub-systems needed and functional

Third harmonic module AH1 (INFN, Milano)




- **18 December 2015:** First *rough* calibration
 - Nominal pulse structure Fill Time: 750 us
 - Flat Top: 650 us
 - Gradient well above nominal 30 MV of VS voltage
 - First quench > 45 MV
- **10 February 2016 :**
 - QL aligned well within the 10% requirement
 - Phases within 15°
- **16 February 2016 :** Back on beam
 - Moved to -180° (wrt on-crest), calibration with beam energy



For details on SC modules see D.Reschke's talk on Thursday THYB01 on 'Performance of Superconducting Cavities for the European XFEL',


Reduced energy spread



Beam in the dump line with large dispersion


3rd harmonic off

3rd harmonic at -16 MV




Optics checks: Trajectory responses and magnet model

- Trajectory response measurements show good matching with theoretical predictions.
- The optics model used in the optics server is correct.
- The magnetic fields of the quadrupole magnets are well known.




Beam Position Monitor Performance (PSI, CEA/IRFU)




- Newly developed BPM system (DESY/PSI/CEA)
- Performs smoothly and beyond specs
- Single shot resolution :
 - 1-5 μm at 500 pC
 - 10 – 50 μm at 20 pC

Resolution of the diagnostics

	at 20 pC	at 500 pC
button BPM	10 μm	5 μm
cavity BPM	10 μm	<2 μm
re-entrant BPM	50 μm	5 μm
Toroid	0.3 pC	0.3 pC






- 1 to **2700** bunches per train at a 10Hz repetition rate
- 2 W to **3.5 kW** beam power at 130MeV and 1nC (10-472kW at 17.5GeV)
- Expected dark current of up to about 30 W at 130MeV and 600 μ s
- Commissioning of Machine protection has first priority!


The machine protection system MPS sets the bunch numbers depending on:


- Status of magnets, screens, valves
- Status of cryogenics and modules
- Losses along the machine (measured with scintillators)

Long Bunch Train Operation





- March 19th : Operation of full bunch train at 250 pC !
- Low losses
- Low activation





- Fine tuning of low-level RF Feedback and Feedforward systems to control RF flat top with beam loading
- Adjustment of laser parameters to avoid charge and trajectory variations




Variation of orbit after gun and in dispersive section


Charge stability much better after laser adjustment


See also the talk from K.P.Przygoda on Thursday THOAA03 on "MTCA based cavity regulation"

Injector operation with 2000 bunches, 0.5 nC




- Transmission through the injector beamline.
- Charge distribution over the pulse train – corrected with the injector laser power






History from March 15th – 21rd




- The operation of the injector with 2700 bunches did not increase the losses.
- The losses are dark current dominated.

Integrated charge so far is ~1.5 C.



Automatic optics matching and emittance measurement




- Projected emittances of ~1.2 mm mrad could be achieved with a 500 pC bunch charge.

e.g.



Plane	Emittance	BMAG
horizontal	1.3 mm mrad	1.16
vertical	1.1 mm mrad	1.04

The BMAG parameter is a measure for the beta function error


- A link to the optics server allows the automatic matching of the optic with a chosen set of quads
- The deformations of the bunch shapes indicate distortions which need further investigations.





Calculated normalized emittances




Emittance measurement with kickers and off-axis screens in the diagnostic section




- Off-axis screens and fast kickers in the diagnostic section allow to measure emittances of single bunches during operation with long bunch trains.




- These measurements are fast and allow also to measure the emittance and mismatch evolution over the bunch train.







OTRC.55.I1




OTRC.56.I1





OTRC.58.I1



OTRC.59.I1




bunch no. 1



- Evolution of the projected emittance, the mismatch and the beam shape over the bunch train.


Courtesy of B. Beutner

Further automated procedures in operation and development




- Phase scans of Gun and modules
- Charge feedback
- Generic scan tool (QE-Map, dipole scans, gun alignment, ...)
- Orbit stabilization
- Dispersion correction

Injector laser stacker (Lyot type)



- Investigate influence and operation of flat top laser pulses.





Gain material	Yb:YAG
Intra burst repetition rate	4.5 MHz, 3 MHz, 1MHz, 100 kHz
Pulse width (FWHM)	Phase 1 (MBI): Short pulse: < 3 ps Long pulse: ~12 ps Phase 2 (DESY): Shaped 26 ps with 2 ps rising edges
Energy per pulse in burst	> 0.7 μ J pP @ 3 ps > 3 μ J pP @ 10 ps

Courtesy of L.Winkelmann, I Hartl


- The laser pulse stacker can be used since April 15.
- Max. Pulse length is 26 ps (FWHM) at the moment.
- The reduced space charge effects should lead to a smaller emittance as shown at the test facility PITZ.
- This effect could not be seen yet. We need more time for further studies.

Preliminary results : Bunch length measurements with EOD




A laser passes through a crystal which is placed near to the beam. The electrical bunch field influence the outgoing laser pulse.

Better suited for measurements after the first bunch compressors – in the injector the bunches are too long for a clear signal.





courtesy of C.Gerth, P.Peier, B.Steffen

Next Steps: TDS System (INR, Moscow)



27

- 3.0 GHz, 3 MW, $< 3 \mu\text{s}$ pulse length
- RF-station is operational
- Structure will be connected these days
- Technical commissioning planned for this month
- Beam commissioning:
 - Establish procedures for automated measurement of slice parameters within bunch train








Next Steps: Laser Heater (Univ. Uppsala)



To avoid micro bunch instabilities a moderate increase of the energy spread is foreseen by means of a laser heater.

A part of the IR laser which drives the Gun laser is coupled out and will be brought to overlap with the electrons in a wiggler magnet



- The IR laser is successfully aligned through the laser beamline (~40m) and wiggler vacuum chamber.
- Next steps:
 - Find transverse and longitudinal overlap
 - Investigate laser-beam interaction, find optimal working points




Injector commissioning goals:

Quantity	Value	Achieved
Macro pulse repetition rate	10 Hz	10 Hz
RF pulse length (flat top)	600 μ s	>600 μ s
Bunch repetition frequency within pulse	4.5 MHz	4.5 MHz
Bunch charge	20 pC – 1 nC	20 pC – 1 nC
Slice emittance	0.4 - 1.0 mm mrad	TDS by May

- Full injector commissioning started Dec. 2015 and will continue until end of July '16
- Sub-systems operate reliably, often beyond specs
- Minimum goal for emittance reached, sufficient for first lasing at XFEL
- Extensive emittance studies needed to investigate the full potential
- TDS and Laser Heater to be commissioned in May
- “Frequency ramping” of the gun in preparation

The started operation of the injector is the result of the tremendous effort of all partners of this project from design, fabrication and testing of the components to installation and commissioning over the last years.

Many thanks to all the colleagues who contributed to this success.



Thank you for your attention!