



JAGIELLONIAN UNIVERSITY
IN KRAKOW



SOLARIS
NATIONAL SYNCHROTRON
RADIATION CENTRE

Performance of Solaris Storage Ring

Adriana I. Wawrzyniak

adriana.wawrzyniak@uj.edu.pl

Solaris National Synchrotron Light Source
Jagiellonian University
Czerwone Maki 98
30-392 Kraków
www.synchrotron.uj.edu.pl



- ❖ Solaris Layout
- ❖ Commissioning goals
- ❖ Commissioning results
- ❖ Current and Lifetime
- ❖ Beam stability
- ❖ Summary

3rd generation light source facility built at the Jagiellonian University Campus in Krakow, Poland. The machine was constructed in 2015 thanks to the unique cooperation with MAXIV Laboratory in Lund, Sweden.



3rd generation light source facility built at the Jagiellonian University Campus in Krakow, Poland. The machine was constructed in 2015 thanks to the unique cooperation with MAXIV Laboratory in Lund, Sweden.

TIME SCHEDULE

April 2010 – project start (Team: 7 persons)

January 2012 – start of the building construction (Team: 15 persons)

May 2014 – building handover & machine installation (Team: 30 persons)

May 2015 – End of installation and start of commissioning (Team: 40 persons)

December 2015 – End of the project


March 2016 – CERIC ERIC collaboration & operational funds for 5 years

May 2016 – PHELIX beamline project approval and funded

April 2016 – start of the UARPES beamline commissioning



April 2017 – Start of the PEEM/XAS beamline commissioning (Team: 50 persons)

Apart of the light source facility the team expertise in all areas of accelerator physics and accelerator and beamline technology has been built.






1.5 GeV Storage ring
12 DBA Cells – 96 m circ.
Space for ID's (10 sections) ~ 3.5 m
10 straight sections for Ids
100 MHz RF system
300 MHz Landau Cavities
Injection dipole kicker
Ramping
In operation since May 2015



600 MeV Linac with RF Thermionic Gun
6 accelerating structures combined in 3 units
Accelerating gradient 20 MeV/m
S-band – 2998.5 MHz
3 RF Units & SLED cavities
In operation since Dec. 2014



Storage Ring Lattice



Electron energy	1.5 GeV
Design current	500 mA
Number of circulating bunches	32
Natural bunch length σ_z /w.	14.2 mm /60 mm
Landau Cavities (LC)	
Natural emittance (bare lattice)	5.982 nmrad
Coupling	1 %
Energy spread (bare lattice)	0.000745
Tunes ν_x, ν_y	11.22, 3.15
Natural chromaticities ξ_x, ξ_y	-22.96, -17.14
Corrected chromaticities ξ_x, ξ_y	+1, +1
Momentum compaction	3.055×10^{-3}
Energy loss/turn	114.1 keV
Momentum acceptance	4%

Optics design by S.C. Leemann - MAXIV

Storage Ring Magnets (mirror symmetric)



Machined from solid iron, 2 half slabs, ~4.5 m, ~7 Tons each slab

Gradient bending magnet with pole-face strips

Combined focusing quadrupole-sextupole magnets

Defocusing sextupole magnets

Multi-coil correction magnets (COD, Skew quads, aux. sextupoles)





Storage Ring Commissioning



Phase I May-July 2015

The goal: to obtain stored beam.

Transfer line commissioning

Injection

First turn

Accumulation

Stored beam

Orbit correction

Phase II September- November 2015

The goal: to reach the design parameters of the bare lattice.

Linear optics correction

Vacuum conditioning

Ramping to 1.5GeV

Orbit correction & BPM calibration

Increasing the current

No IDs in operation

Phase III March-December 2016

The goal: to reach the usable beam current for experiments.

Lattice optimisation with undulator in place

Beam based alignment

Injection efficiency optimisation


Lifetime improvements

Landau cavities tuning



Beamlines commissioning



Injection at the energy of 525 MeV with the repetition rate of 1 Hz. The injection of 200 mA can be done in 140 s and ramping - in 238s. Injection efficiency – 30%.




Bunch train length ~180 ns in the transfer line.






Phase advance and tune measurements done by exciting the beam with the kicker and register the TbT data on BPMs.





The average phase advance is 114 deg in the horizontal and 30 deg in the vertical plane



Tune corrected to the design values 11.22, 3.15





Chromaticity measurements for two optics



Chromaticity	Nominal 331/333	Measured
ξ_x	+2/+1	+1.41/+0.89
ξ_y	+2/+1	+1.56/+0.90

For orbit correction **36 button beam position monitors (BPMs)** with Libera Brilliance+ electronics, **36 horizontal and 36 vertical correctors** are used. **The maximum kick angle** of correctors is **0.25 mrad (10 A)**. To correct the orbit the measured response matrix and **SVD** algorithm implemented in **MML** is used.




After BBA BPM offsets <0.6 mm
Some of correctors are close to the saturation


Closed Orbit	Without Correction	With correction	After BBA
x_{rms}	701 μm	200 μm	160 (66.51) μm
y_{rms}	1090 μm	170 μm	55.42 μm

A. Kisiel, MOPIK090

Horizontal β function



Vertical β function



Quadrupole scan

$$\beta_{x,y} = \pm 4\pi \frac{\Delta Q_{x,y}}{\Delta k}$$

ORM method

$$\beta_{x,y} = 2 \cdot \tan(\pi Q_{x,y}) \cdot \frac{\Delta x_{CM}}{\Delta \theta}$$


LOCO

$$\chi^2 = \sum_{i,j} \frac{(R_{i,j}^{meas} - R_{i,j}^{model}(\Delta k))^2}{\sigma_i^2}$$


Method	Hor. beating	Vert. beating
QUAD	26.84%	33.52%
ORM	13.14%	23.49%
LOCO	16.45%	11.73%


The LOCO studies has revealed that the quad strength errors are up to 0.8 % for DBA2. The shunting of the magnets is planned.

The dispersion measurement has been done by changing the RF frequency and recording the closed orbit.




The horizontal dispersion is close to the nominal. The vertical dispersion originates from the (roll angle) misalignment of quadrupole and sextupole magnets.







Synchrotron tune vs. total RF voltage.



$$P_{forw} - P_{refl} = P_{cav} + \frac{IU_0}{e}$$


$$Q_s^2 = \frac{\alpha_c h}{2\pi E} \sqrt{e^2 V_{RF}^2 - U_0^2}$$

	Designed	Measured
U_0 [keV/turn]	114.1	103.7 (12.3)
E [GeV]	1.5	1.45 ()
P_{cav} [kW]	49	39 (1)
Φ_s [deg]	168	167.4




$$\delta_{acc,RF} \approx \frac{2Q_s}{h\alpha_c} \sqrt{1 + \left(\phi_s - \frac{\pi}{2}\right) \tan(\phi_s)}$$

RF acceptance $3.7\% \pm 0.3\%$
 $V_{RF}=480\text{kV}$




Normalized average pressure vs. beam current




The average pressure in the storage ring with 250 mA of a stored current at 1.5 GeV is $2.2 \cdot 10^{-9}$ mbar.

A. Marendziak, WEPAB068

Analysis of normalized average partial pressures over integrated current for section R1-01.





The bam lifetime is still increasing with the accumulated beam dose.



Maximum injected current over 600 mA.
Maximum current at full energy over 400 mA.






The bam lifetime is still increasing with the accumulated beam dose.



Maximum injected current over 600 mA.
Maximum current at full energy over 400 mA.

Lifetime measurements @ 1.5 GeV, I=200 mA











	without LC	with LC
Elastic scattering τ_{elastic}	22.24	23.66 h
Inelastic scattering $\tau_{\text{inelastic}}$	37.45 h	43.57 h
Touschek lifetime τ_{Touschek}	21.13 h	68.81 h
Total lifetime τ_{tot}	8.41 h	12.54 h

Physical acceptance:
 $A_x(\delta) = 15.68 \text{ mm} \cdot \text{mrad}$
 $A_y(\delta) = 3.77 \text{ mm} \cdot \text{mrad}$



Closed orbit changes from injection to injection






In the horizontal plane the standard deviations calculated from injection and ramping dataset are comparable reaching 200 μm and the deviation of final-corrected orbit is significantly lower ($\sim 30 \mu\text{m}$).


In the vertical plane, for the injection orbits the deviation is up to 300 μm , after-ramping dataset - up to 100 μm and below 10 μm in corrected orbits at final energy.

The vertical position drift of electron (red) and photon (blue) beam monitored over 25h without orbit correction.



Temperature oscillations in the range of 1.5°C in the storage ring have impact on beam stability.

The temperature (red) and the photon beam oscillations monitored over 30 min with applied orbit correction.



- ★ A good performance of the Solaris light source has been achieved.
- ★ **Injection** to the storage ring occurs at **525 MeV** and the **beam is ramped** to the operating energy of **1.5 GeV without losses**.
- ★ The **injection efficiency** has been improved reaching now **30%** and is still under optimisation. The chopper is tested and planned for installation during summer.
- ★ **The optics** was corrected **close to the design** one. However some adjustments are still needed.
- ★ The beta functions were measured with 3 different methods, revealing a **beta beating** in both planes in the order of **several %**. The optics correction with the local shunting is under way, these should also improve the closed orbit and relax the correctors strength.
- ★ Studies of **synchrotron tune** have shown that Solaris storage ring is operating at c.a. **3.3% lower energy** than expected.
- ★ The **maximum current** ramped to the final energy of **1.5 GeV** is above **400 mA** with the total **lifetime of 8 h**.
- ★ **Tuning of the Landau** cavities **improved** the **Touschek lifetime** by factor of 3 and cured some instabilities.
- ★ The **closed orbit** can be **restored** from injection to injection with **tens of microns** range with the orbit correction applied.
- ★ **Temperature oscillations** in the range of **1.5°C** in the storage ring have **impact on beam stability**. Major changes in the cooling water system are planned in the near future to improve the thermal stability at Solaris.

- ★ Commissioning of the UARPES Beamline by 2018
- ★ Commissioning of the PEEM/XAS Beamline by 2018
- ★ Installation & commissioning of the PHELIX beamline by 2020
- ★ Installation & commissioning of the XMCD beamline (former MAXII I1011)
- ★ USER OPERATION from the beginning of 2018
- ★ Installation of diagnostic beamline for emittance measurements

MAX IV TEAM

**Elettra, Sincrotrone Trieste
Machine Advisory Committee
A. Wrulich, PSI, Switzerland
R. Walker, J. Kay, Diamond, UK
A. Nadj, SOLEIL, France
Dieter Einfeld, ESRF, France
G. Rehm, Diamond, UK
F. Perez, ALBA, Spain
SOLARIS Team**



First angle-resolved experiment at the UARPES beamline.... Graphene on SiC(0001) – Dirac cone


Mean ring current: 40 mA

Photon energy 50 eV

3D mode – time 4h 30 min (full dataset)

Electron energy resolution ~ 20 meV

Room temperature



Piotr Ciochon, Mariusz Garb, Karolina Szamota-Leandersson, Jacek Kolodziej



Thank you for the attention!

