

PAUL SCHERRER INSTITUT



Thomas Schietinger (on behalf of the SwissFEL team) :: Paul Scherrer Institut

# Towards full performance operation of SwissFEL

9th International Particle Accelerator Conference,  
Vancouver, BC, Canada, 28 April - 4 May 2018

- SwissFEL overview
- The big picture:  
machine evolution at a glance
- First pilot experiments
- Smaller pictures:  
status and plans for key systems
- Beam dynamics progress
- FEL setup and characterization
- Schedule Aramis (hard X-rays)
- Outlook Athos (soft X-rays)




## Athos:

Soft X-ray FEL,  $\lambda=0.65-5.0$  nm  
 Variable polarization, Apple-X undulators  
 First users 2021

First construction phase  
 2013-16

Second construction phase  
 2017-20




## Aramis:

Hard X-ray FEL,  $\lambda=0.1-0.7$  nm  
 Linear polarization, variable gap,  
 in-vacuum undulators  
 First users 2018

### Main parameters:

Photon wavelength	0.1-5 nm
Photon energy	0.2-12 keV
Pulse duration	1-20 fs
Electron energy	5.8 GeV
Electron bunch charge	10-200 pC
Repetition rate	100 Hz


# SwissFEL experimental areas




# The big picture...




# SwissFEL Machine Evolution




# SwissFEL Machine Evolution







# SwissFEL Machine Evolution




# SwissFEL Machine Evolution




# SwissFEL Machine Evolution




# SwissFEL Machine Evolution





# SwissFEL Machine Evolution




# SwissFEL Machine Evolution



# SwissFEL Machine Evolution



# First SwissFEL sample (Bernina endstation)








# First pilot experiment at SwissFEL!

Experiment time: 27 Nov. - 4 Dec. 2017  
 Experimental station Bernina (ESB)  
 Collaboration: Univ. Rennes, ESRF, PSI  
 M. Cammarata, H. Lemke, G. Ingold et al.

PSI press release:  
[www.psi.ch/media/first-experiment-at-swissfel-carried-out-successfully](http://www.psi.ch/media/first-experiment-at-swissfel-carried-out-successfully)

- Pump-probe investigation of the transition between metallic ( $\lambda$ ) and semi-conducting ( $\beta$ ) phase of titanium pentoxide ( $\text{Ti}_3\text{O}_5$ )
- Diffraction on nanocrystals, Jungfrau detector
- Pump: 800 nm, 42 mJ/cm<sup>2</sup> laser
- Probe: FEL 3rd harmonic 6.6 keV (fundamental 2.2 keV, 220  $\mu\text{s}$ )



# First X-ray emission spectra at SwissFEL



Experiment time: 11-17 Dec. 2017

Experimental station Alvra (ESA)

Collaboration: Inst Nucl. Phys. PAN Krakow, Univ. Bremen, PSI

J. Szlachetko, J. Czapla-Masztafiak, M. Kwiatek, M. Vogt, Ch. Milne. et al.


- UV photo-induced charge transfer in Cu/P based OLED system
- Time-resolved X-ray emission spectroscopy (XES)
- Pump: 355 nm,  $\sim 100$  mJ/cm<sup>2</sup> laser
- Probe: FEL fundamental 2.34 keV (250  $\mu$ J)



# Characterization of pump-probe timing jitter

Relative Bragg intensity as a function of pump-probe delay time, measured on Bi(111) film (modulation from optically pumped phonons, benchmark system)


Bernina, 21 March 2018




# First SwissFEL lasings

Date	Purpose	Electron energy	Photon wavelength (energy)	Photon pulse energy	Comments
Dec. 2016	Inauguration	380 MeV	24 nm (50 eV)	Not measured	Backup gun laser; single-stage comp.
May 2017	IPAC'17	910 MeV	4.1 nm (300 eV)	30 $\mu$ J	Backup gun laser; single-stage comp.
Aug. 2017	1st photonics commissioning	1.62 GeV	1.28 nm (970 eV)	9.5 $\mu$ J	Backup gun laser; single-stage comp.
Nov. 2017	1st pilot experiment (Bernina)	2.45 GeV	0.55 nm (2.2 keV)	220 $\mu$ J	Main gun laser; dual-stage comp.; laser heater, tapering
Dec. 2017	2nd pilot experiment (Alvra)	2.6 GeV	0.54 nm (2.3 keV)	250 $\mu$ J	Main gun laser; dual-stage comp.; laser heater, tapering


# SwissFEL Machine Evolution



# SwissFEL Machine Evolution




# SwissFEL Machine Evolution




## Status

- **RF gun:**
  - Fully commissioned, 7.1 MeV nominal energy
  - Spare gun in production
- **Cathode:**
  - Cs<sub>2</sub>Te coated copper cathode installed since July 2017.
  - Quantum efficiency stable at about 0.7% with uniform distribution around the laser spot.



laser spot size (1 mm Ø)






## Status

### • Gun laser system:

- Solid state Yb:CaF<sub>2</sub> chirped pulsed amplifier with excellent stability and uptime.
- Variable circular aperture allows optimization of beam size on cathode (low emittance).
- Approximate flat top profile with pulse stacking – beam based profile optimization.
- Backup laser (Nd:YLF) with Gaussian profile available – switching is instant.

- *Standard operating procedure* for routine gun-laser check – fundamental for stability and reproducibility of the facility!




*Gun laser longitudinal profile optimization (with RF deflected electrons)*

## Status

- **Gun laser system:**
  - Solid state Yb:CaF<sub>2</sub> chirped pulsed amplifier with excellent stability and uptime.
  - Variable circular aperture allows optimization of beam size on cathode (low emittance).
  - Approximate flat top profile with pulse stacking – beam based profile optimization.
  - Backup laser (Nd:YLF) with Gaussian profile available – switching is instant.
- *Standard operating procedure* for routine gun-laser check – fundamental for stability and reproducibility of the facility!

## To do

- Establish 100 Hz operation.
- Systematic comparison pulse-stacked versus stretched Gauss profile.
- UV arrival time monitor/feedback.
- Dual pulse generation setup (for soft-X-ray beamline).
- Procurement of identical backup laser system.




*Gun laser longitudinal profile optimization (with RF deflected electrons)*



# SwissFEL key system: C-band linac

ScandiNova

AMPEGON



- 26 C-band modules (5.7 GHz) with 4 structures each
- Barrel Open Cavity (BOC) RF pulse compressors
- Modulators:
  - Ampegon (Linac-1, Linac-2)
  - Scandinoa (Linac-3)
- Klystrons: Toshiba
- 50 MW for 3  $\mu$ s, 370 kV/344 A
- ca. 200 – 280 MV per station (depending on conditioning status)




# SwissFEL key system: C-band linac

## Status


- **13 (out of 26) modules on beam**
  - all of linac-1 (9 modules, running 19° off-crest)
  - 1 module in linac-2
  - 4 modules in linac-3
- All modules currently run at 100 Hz (beam only at 10 Hz)
- Currently operating at a total energy of **3.0 GeV** (0.3 GeV from injector), with about 0.5 GeV reserve.

## To do


- Commissioning and conditioning of remaining modules!
- Current plan for energy increase:
  - **3.7 GeV** by mid May (**16 modules**)
  - **4.7 GeV** by mid July (**22 modules**)
  - **5.8 GeV** by mid September (**24 modules**)
  - with appropriate reserve!
- Beam tests at increasing repetition rate (25, 50, 100 Hz) – goal: 100 Hz beam operation by September 2018!



# SwissFEL key system: Aramis undulator line



- In-vacuum, variable-gap undulators “U15”
- Undulator period 15 mm
- Nominal gap 4.5 mm for  $K = 1.2$
- Array of 1060 permanent magnets (NdFeB with diffused Dy) per module
- 13 modules of 4 m length
  - Total length 65 m
  - Active length 52 m





## Status

- Basic commissioning and alignment of undulator line done
  - corrector-based electron-beam based alignment (BBA) done
  - alignment of undulators to BBA orbit with alignment quads
- Photon based procedure for undulator fine tuning implemented and tested
  - Using spontaneous radiation from a single undulator
  - Monochromator, photodiode/MCP for photon detection
  - Optimization of K values, undulator height and pitch


## To do

- Systematic comparison of electron- and photon-based measurements
  - Some variations in contributions from modules not yet understood.
  - Some photon beam properties not yet understood (spatial chirp).
- Completion of photon-based fine tuning.
- Establishment of final BBA procedure





## Status

- For photon beam delivery:
  - **Resonator cavity beam-position monitors** (cBPMs) drive (slow) **orbit feedback** everywhere and **energy feedback** at three locations (BC1, BC2, energy collimator).
  - **Bunch compression monitor** based on THz detection drives **partial compression feedback** (BC1 only so far) – *next slide*
- For beam setup:
  - Use scintillating **YAG screens** (emittance)
  - with **RF deflector** for longitudinal measurements (bunch length, slice emittance)
- Initial commissioning of **bunch arrival time monitor (BAM)** – *next slide*
- Initial commissioning of **wire scanners**
- **Charge and loss monitors** fully commissioned



## To do

- Commissioning compression monitor at BC2 (coherent diffraction radiation, later IR spectrometer)
- Commissioning bunch arrival time monitor and integration into global feedback.
- Wire scanner commissioning
- 100 Hz operation
- Advanced commissioning of all systems...




### Bunch compression monitor

- Measure THz radiation from last compression dipole edge with Schottky diodes.
- Set of filters for spectral range selection.
- Pulse-to-pulse data available → feedback on FEL signal!

## Bunch arrival-time monitor


- First bunch arrival-time monitor yielding data.
- Measurement resolution is  $\sim 5$  fs.
- Measured (preliminary) arrival time jitter after BC1 is  $\sim 35$  fs (will improve with new X-band preamps installed last week!)





# Beam dynamics progress (1)

- **Optics and emittance**

- After initial problems optics now well understood.
- Emittance of uncompressed beam in injector optimized to  $\leq 250$  nm (projected),  $\approx 150$  nm (slice) for 200 pC bunch charge (10 ps rms bunch length).



# Beam dynamics progress (2)




Example of bunch-length measurement after BC1  
(two zero crossings of RF deflector)

## • Compression setup

- Systematic compression in BC1 down to  $\approx 120$  fs (rms) bunch length (compression factor  $\approx 20$ ) with two compression “knobs” constructed from S-/X-band amplitudes and phases. Slice emittance under control.
- Preliminary setup of dual stage compression (BC1 and BC2) with C-band deflecting cavity (available since Jan. 2018) for final bunch length of 50 fs (rms).
- Systematic optimization of dual stage compression still in progress...

- **Laser heater**


- Initial commissioning done: transverse and longitudinal overlap determined.
- Characterization of laser-heater induced energy spread, also time-resolved (“heating shape”).
- Detailed commissioning / characterization still needed!



- **FEL setup:**

After optics and compression setup and verification, we apply the following steps for optimal FEL output:

- 1) Optimization of *pre-saturation taper* (linear)
  - Compensate for energy loss from wakefields
- 2) Adjustment of K values and phase shifters for uniform gain (if necessary)
- 3) [Optimize laser heater energy for max. pulse energy]
- 4) Optimization of *post-saturation taper* (linear and quadratic)
  - Compensate for energy loss from wakefields and from FEL
- 5) Readjustment of K values and phase shifters for uniform gain (if necessary).
- 6) Random walk optimization of electron orbit in undulator section.



Gain curve (gas detector), 14 March 2018


- **FEL characterization:**

- Gain length around 2 m, in rough agreement with expectation
- Photon pulse energy at saturation: 250 μJ for K = 1.2 at 2.6 GeV (2.3 keV photon energy) and 350 μJ for K = 1.45 at 2.3 GeV (2.0 keV).

# Example: FEL performance during pilot week


- Week 12/2018
- Second experiment at Bernina end station
- 2.5 GeV electrons, 2 keV photons ( $K = 1.45$ )
- Measurements on the 3rd harmonic (6 keV)

- Bunch charge in beamdump (pC)
  - Photon pulse energy ( $\mu\text{J}$ )
- Mon, 19-Mar, 18:00 – Mon, 26-Mar, 18:00




- Overall ~90% uptime
- Some downtime due to user requests to change setup / beam parameters

# SwissFEL Machine Evolution





# Aramis schedule (hard-X-ray line)



# Outlook Athos (soft-X-ray line)

**Flexible** undulators and chicanes for a **compact** and **bright** beam line!




Aramis line  
(hard X-ray)

Athos line  
(soft X-ray)

*SwissFEL still under construction...*


# Outlook Athos (soft-X-ray line)



Athos U38 undulator concept

- Redesigned soft-X-ray undulator line featuring **16 Apple-X U38** undulators:
  - full polarization control
  - independent K and polarization control
  - transverse gradient undulator (TGU)
  - symmetric force distribution (gap = slit)
- Small **interundulator magnetic chicanes** to enable
  - Optical klystron mode
  - High-brightness mode
  - Terawatt-attosecond mode
- One large **magnetic chicane** for two-color operation (delay between -10 fs and +500 fs)

- Custom-designed **resonant kicker magnet** to distribute bunches separated by 28 ns.
- Installed and successfully tested in March.



# Outlook Athos (soft-X-ray line)

**Flexible** undulators and chicanes for a **compact** and **bright** beam line!

## Athos schedule:

- Athos dogleg ready for commissioning by June 2018
- U38 module prototype delivery in June 2018
- Delay chicanes in procurement
- Undulator installation Jan. 2019 – March 2020
- **First pilot experiment end 2020**
- **User operation from 2021**



- SwissFEL has reached its 2017 milestone of first pilot experiments (with reduced parameters – 2.2 keV photon energy at 10 Hz).
- Systems and beam development program on track to reach nominal beam parameters by the end of 2018 (12.4 keV photon energy at 100 Hz).
- Regular user operation to start in January 2019!
- New soft-X-ray beamline Athos on track for first users in 2021.

