



# The FRIB SC-Linac: Installation and Phased Commissioning

Jie Wei

On Behalf of FRIB Accelerator Team & Collaboration

SRF 2019, Dresden, July 1, 2019

**MICHIGAN STATE**  
UNIVERSITY



U.S. DEPARTMENT OF  
**ENERGY**

Office of  
Science

# Outline

- Introduction
- Phased beam commissioning and strategic planning
- Design and construction evolution
- Installation and preparation
- Operations coordination and maintenance infrastructure
- Summary



# Introduction



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University

# Facility for Rare Isotope Beams


## Project On Track for Early Completion in 2021

- FRIB Project constructs a \$730 million national user facility funded by the U.S. Department of Energy Office of Science (DOE-SC), Michigan State University, and the State of Michigan
- Planned completion date is June 2022, managing to early completion in 2021
- FRIB will be a DOE-SC scientific user facility for rare isotope research supporting the mission of the Office of Nuclear Physics in DOE-SC




**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University

# FRIB Enables Scientists to Make Discoveries




## Properties of atomic nuclei

- Develop a predictive model of nuclei and their interactions
- Many-body quantum problem: intellectual overlap to mesoscopic science, quantum dots, atomic clusters, etc.




## Astrophysics: What happens inside stars?

- Origin of the elements in the cosmos
- Explosive environments: novae, supernovae, X-ray bursts ...
- Properties of neutron stars



## Tests of laws of nature

- Effects of symmetry violations are amplified in certain nuclei



## Societal applications and benefits

- Medicine, energy, material sciences, national security

Science is aligned with national priorities articulated by

- Nuclear Science Advisory Committee to DOE and NSF *Long Range Plan for Nuclear Science* (2015)
- National Research Council *Decadal Survey of Nuclear Physics* (2012)
- National Research Council *Rare Isotope Science Assessment* report (2006)

# Basic Research in Rare Isotopes Leads to Applications for Society

## ■ Medical applications

- Isotopes for medical research
- Medical imaging and treatment of cancer and tumors




## ■ Energy

- Reliable calculation of fission and energy generation
- Allow mechanisms of radiation damage to be studied in detail
- Sensitive probes for the development of new materials, e.g. lithium-film batteries



## ■ Homeland security and defense

- Detectors at borders and throughout the country to detect nuclear material and components
- Nuclear scanning techniques to screen cargo and luggage
- Nuclear forensic methods to track and trace nuclear material



## ■ Workforce


- Development of talent for technical, medical, security, and industrial fields



# FRIB Optimized for Science

## with Fast, Stopped and Reaccelerated Rare Isotope Beams


- Key feature is 400 kW beam power for all ions ( $8\text{p}\mu\text{A}$  or  $5 \times 10^{13} \text{ }^{238}\text{U/s}$ )
- Separation of isotopes in-flight provides
  - Fast development time for any isotope
  - Beams of all elements and short half-lives
  - Fast, stopped, and reaccelerated beams



# FRIB at Accelerator Power Frontier

## among Three Major Frontiers: Energy, Power, Brightness


- FRIB will provide more beam power by two-to-three orders of magnitude over existing heavy-ion facilities
- Past experience for less-complex proton machines indicates steep learning curve
- Successful early operation is key to achieving desired power ramp-up profile
- Beam losses will limit power ramp-up, mitigation takes time and experience




# FRIB Project at Michigan State University

## Project of \$730M (\$635.5M DOE, \$94.5M MSU)

- 2008-12: DOE selects MSU to establish FRIB
- 2009-6: DOE and MSU sign corresponding cooperative agreement
- 2010-9 CD-1: conceptual design complete & preferred alternatives decided
- 2013-8 CD-2/CD-3a: performance baseline, start of civil construction & long lead procurement
- 2014-8 CD-3b: start of technical construction
- 2022-6 CD-4: construction completion




# FRIB Accelerator Complex Subsystems








# FRIB Accelerator Complex Subsystems




ECR ion source



# FRIB Accelerator Complex Subsystems



# FRIB Accelerator Complex Subsystems



ECR ion source

QWR cryomodules

RFQ

Charge stripper

- Instrumentation
- Liquid Nitrogen Reservoir (70 K)
- Four 1.5W Cryocoolers (Thermal Links) and Heat Exchanger
- HTS Leads
- Liquid Helium Reservoir (4.2 K)
- Links
- Cold Mass with Coils Enclosed

(Energy Upgrade)

Linac Segment 3

Linac Segment 1


Linac Segment 2

Cold Box


Warm Compressor

F

# FRIB Accelerator Complex Subsystems




# FRIB Accelerator Complex Subsystems







ECR ion source


QWR cryomodules



HWR cryomodules



# FRIB Accelerator Complex Subsystems



Fragment separator

ECR ion source

QWR cryomodules

Target

RFQ

HWR cryomodules

Charge stripper


- Instrumentation
- Liquid Nitrogen Reservoir (70 K)
- Four 1.5W Cryocoolers (Thermal Links) and Heat Exchanger
- (HTS Leads)
- Liquid Helium Reservoir (4.2 K)
- Links
- Cold Mass with Coils Enclosed

(Energy Up) Segment 3

Cold

F

# FRIB Accelerator Complex Subsystems



Fragment separator

ECR ion source

QWR cryomodules

Target

RFQ

HWR cryomodules

Charge stripper

Stopped Beam Area    Reaccelerated Beam    0    25    50 Meters

- Instrumentation
- Liquid Nitrogen Reservoir (70 K)
- Four 1.5W Cryocoolers (Thermal Links) and Heat Exchanger (HTS Leads)
- Liquid Helium Reservoir (4.2 K)
- Links
- Cold Mass with Coils Enclosed

(Energy Up)    Segment 3

Cold

1 meter

F

# Civil Construction: March 2014 - March 2017

Groundbreaking – March 2014



March 2015




March 2016



Beneficial Occupancy – 2017



# Accelerator Tunnel Installation Proceeding



- FRIB linac tunnel is  $\sim 10$  m underground for prompt radiation shielding
- Accelerates all stable ions (proton to uranium) above 200 MeV/u with upgrade to 400 MeV/u in continuous wave (CW) or pulsed modes


# Phased beam commissioning and strategic planning



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University


# 2017: Front End Beam Commissioned (ARR1)

## Integrate Warm Systems with New Civil Infrastructure




SCS1:VD\_D0739:imac

asyn port	Image1
Plugin type	NDPluginStdArrays
Array port	WARP1
Array address	0
Enable	Enable
Min. time	0.000
Callbacks block	No
Queue size/free	3
Array counter	0 / 2860527
Array rate	5.00
Dropped arrays	0
# dimensions	3
Array Size	1920 1200 0
Data type	UInt16
Color mode	Mono
Bayer pattern	RGBB
Unique ID	
Time stamp	
Attributes file	
Array callbacks	Disable
asyn record	



Argon beam at end of U-LEBT  $^{40}\text{Ar}^{9+}$



- Beam based measurement & RF calibration in agreement within 1%



# 2018: Accelerate Beams $> 2 \text{ MeV/u}$ (ARR2) Integrated Cryogenic and Cryomodule Systems




Temporary diagnostics station containing multiple instrumentation devices



July 10, 2018,  $\text{Ar}^{9+}$  beam accelerated by cryomodule 1 – 3 to  $2 \text{ MeV/u}$

# 2019: Accelerate Beams > 20 MeV/u (ARR3)


## FRIB Became World's Highest Energy CW Hadron Linac



# Phased Commissioning towards Completion

2020 Goal: Accelerate Beams > 200 MeV/u (ARR4)


Phase	Area with beam	ARR	
ARR1	Ion source, Low Energy Beam Transport (LEBT), RFQ, Medium Energy Beam Transport (MEBT)	07/2017	✓
ARR2	Linac Segment (LS) 1 ( $\beta=0.041$ cryomodules)	05/2018	✓
ARR3	Rest of LS1 and first dipole of Folding Segment (FS) 1	02/2019	✓
<b>ARR4</b>	<b>Rest of FS1, LS2, and part of FS2 to straight dump</b>	<b>03/2020</b>	
ARR5	FS2, LS3, part of Beam Delivery System (BDS) to straight dump	12/2020	
ARR6	BDS, target hall pre-separator	09/2021	
ARR Final	Prior post-start Items, vertical pre-separator (outside target hall), reconfigured A1900, entire facility	12/2021	



# Strategy Facilitating Phased Commissioning

## Allowing Each Area at Totally Different Project Phase

- LS1: operations; LS2: commissioning; LS3: construction; ESD: design



# Strategy Facilitating Phased Commissioning

## Allowing Each Area at Totally Different Project Phase

- LS1: operations; LS2: commissioning; LS3: construction; ESD: design

Fragment Separator

Production Target

Folding Segment 1





Linac Segment 3 Segment 2

Linac Segment 1

Front End

Linac Segment 2

Warm Compre




# Design and construction evolution



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University

# Integrated Cryogenics



- Dramatic recovery over early setback in the attempt to procure a turn-key system
- An integrated design of the cryogenic refrigeration, distribution, and cryomodule systems is key to efficient SRF operations
  - Ganni cycle: floating pressure process
  - Distribution lines segmented
  - Cryomodules connected with U-tubes: maintenance
  - 4-2 K heat exchangers housed inside cryomodules

# Helium Refrigeration System Operational

## All Cryomodules in Linac Segment 1 Cooled Down to 2 K



2 K cold box commission on December 2018




2 K cold box installation August 2018



Both Linac Segment 1 and 2 cryo-lines cool down since March 2019

# Bottom Up Cryomodule

- Facilitate assembly efficiency; simplify alignment; and allow U-tube cryogenic connections for maintainability
  - Resonators and solenoids supported from the bottom
  - Cryogenic headers are suspended from the top for vibration isolation



- All resonators operate at 2 K
- All solenoids operate at 4.5 K
- Local magnetic shielding for  $1.5 \mu\text{T}$  remnant field

**WETE5:** S. Miller et al, FRIB cavity and cryomodule performance, comparison with the design and lessons learned

# Six Cryomodule Assembly Bays in Parallel


## Producing ~ 1.5 Cryomodules Per Month at MSU

**THP098: C. Compton et al, The FRIB superconducting cavity production status and findings concerning surface defects**





# Six Types of Cryomodules Being Assembled

$\beta=0.041, 0.085, 0.29, 0.53$  for Baseline;  $\beta=0.65$  for Upgrade



# Low- $\beta$ SRF

Development Intensified since 2011 Overcoming Early Challenges



- Superconducting RF starting from 0.5 MeV/u
- Optimum performance at low production cost
  - geometry; material; mechanical solutions
- Designs fully validated
  - Vertical Dewar tests
  - Integrated tests of the cavity, power coupler, tuner, and ancillary systems
  - Assembled cryomodule 100% tested in bunker
  - Beam tested

# MSU/FRIB Contributions to SRF 2019

**MOP071:** J. Popielarski *et al*, FRIB coupler performance and lessons learned.

**MOP072:** K. Saito *et al*, FRIB solenoid package in cryomodule and local magnetic shield.

**TUP089:** M. Xu *et al*, FRIB LS1 cryomodule's solenoid commissioning.

**TUP090:** S-H. Kim *et al*, Performance of quarter wave resonators in the FRIB superconducting driver linear accelerator.

**TUP091:** C. Compton *et al*, Production Status of Superconducting Cryomodules for the Facility for Rare Isotope Beams.

**TUP092:** K. Elliott *et al*, Experiences of superconducting radio frequency coldmass production for the FRIB linear accelerator.

**TUP093:** E. Matzgar *et al*, Summary of FRIB cavity processing in the SRF coldmass processing facility and lessons learned.

**WETEA5:** S. Miller *et al*, FRIB cavity and cryomodule performance, comparison with the design and lessons learned.

**THP061:** W. Hartung *et al*, Performance of FRIB production quarter-wave and half-wave resonators in Dewar certification tests.

**THP062:** W. Chang *et al*, Progress in FRIB cryomodule bunker tests.



**THP063:** S. Shanab *et al*, Investigating the possibility of 1.3 GHz SRF cavity for medium-beta heavy ion multi-charge-state beams.

**THP098:** C. Compton *et al*, The FRIB superconducting cavity production status and findings concerning surface defects.

# Machine Protection System (MPS)

## Low Sensitivity & Short Range of Intense Heavy-ion Beams

- Uranium ion stopping range is about 30 times shorter than proton's
  - Uranium ion energy deposition density in material is more severe than protons
- Uranium beam is about 30 times more difficult to detect than protons
  - Further complicated by signal interference in the folded layout
- MPS of multi time scale is needed to mitigate both acute & chronicle beam loss
  - Both prompt damage and long-term degradation of SRF resonators
- Innovative detection techniques developed
  - Halo monitor ring and thermometry sensors for high-sensitivity loss detection
  - Current monitoring modules for critical magnet power supply inhibition




Cold BPM and Fast Thermometry Sensors (RTDs) installed on FRIB-1 cryomodule

# Fast Machine Protection Validated

## Differential BPM Readings Inhibits Beam within 35 $\mu$ s

- Validated chopper and chopper monitoring system to limit beam power
- Commissioned differential BPM system for fast ( $< 35 \mu$ s) MPS
- Halo monitor ring provided rich signal for both ion and electrons
- Thermometry sensors responded to beam loss with 0.1 K sensitivity
- Run permit system under commissioning

Mode	Time	Detection	Mitigation
FPS	$\sim 35 \mu$ s	LLRF controller Dipole current monitor Differential BCM Ion chamber monitor Halo monitor ring Fast neutron detector	LEBT bend electro-static deflector
RPS (1)	$\sim 100$ ms	Vacuum status Cryomodule status Non-dipole PS Quench signal	As above; ECR source HV
RPS (2)	$> 1$ s	Thermo-sensor Cryo. heater power	As above



# Installation and preparation





**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University


# Personnel Protection System Establishment

## Determine Accelerator & Operations Safety Envelope (ASE/OSE)

- Oxygen Deficiency Hazard (ODH) mitigation for cryogenic environment
  - No nitrogen cryogen allowed in the FRIB tunnel
  - Separate ODH zones for cryo-plant, tunnel, rack room
- Access Control System to FRIB tunnel: 10 m underground for shielding
- Radiation Control System for prompt radiation and fault conditions
- Physically separated PPS controls network for reliability, cyber security



# Microphonic Mitigation Provisions at Resonator, Cryomodule, Cryogenics Design





- Previsions in compressor design & installation verified by tunnel vibration measurements
- Detailed resonator and cryomodule designs
- Additional design features
  - QWR mechanical damper
  - Cryo-header attachment to top cover to suppress low freq. mechanical modes
  - All resonators run at 2 K
- Promptly resolved cavity locking issue upon initial cool down
  - Iteration on valve controls logic
  - Provision for liquid helium supply from 10,000 liter Dewar



# Survey and Alignment

## “Bottom-up” Cryomodule Design Minimizes Manual Intervention

- Satisfactory beam commissioning achieved without in-field alignment adjustments of individual sub-components (resonators & solenoids)
  - Correctors at  $< 25\%$  full strength to control orbit deviation  $< \pm 1$  mm
- Standardized fabrication tolerance & assembly procedure executed
  - Fiducials measured during coldmass assembly
  - Thermal offset corrections account for cool-down
  - Least-square fit line through magnetic centers of the solenoids to characterize CM alignment




# Cryogenic Installation and Cool Down



- Conducting final assembly and tests on site avoids complications
- Phased cool down commissioning of cryo-distribution lines to support various phases of accelerator beam commissioning
- Individual cryomodule installation, tests, and cool down (dictated by controls and interlock configuration)




# Device energization and RF conditioning





- Rigorous tests and thorough preparation ensures prompt SRF commissioning
  - Resonators, couplers, solenoids etc. 100% cold tested at working temperature
  - Cryomodules 100% bunker tested
- Cryomodule (containing up to 8 QWRs and solenoids) typically commissioned at the rate of one per day
- All SRF resonators and SC solenoids perform above design specifications

TUP090: S-H. Kim *et al*, Performance of quarter wave resonators in the FRIB superconducting driver linear accelerator.

# Low-level RF Controls and Automation



- Amplitude and phase errors:
  - Achieved  $< \pm 0.1\%_{pk-pk} < \pm 0.2^\circ_{pk-pk}$
  - Specifications:  $< 1\%_{pk-pk}, < \pm 1^\circ_{pk-pk}$
- Automated turn-on of resonators
  - ~ 30 s per resonator
  - Turn on all 104 QWR cavities in ~ 20 min.
- No issue with frequency locking



# Operations coordination and maintenance infrastructure



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University

# Interlaced Installation and Commissioning

## Demands Operational Discipline and Close Coordination

### ■ Commissioning shifts

- Access Control System prevents access into the shielded enclosure while the Radiation Control System interlock ensures that there is no prompt radiation through temporary penetrations, including the transport shaft and unsealed conduits
- Before the transition to an installation shift, a radiation survey is done and areas of radio-activation are secured

### ■ Installation shifts

- Daily work control planning is implemented for all tasks in the linac tunnel, with specified locations, times, and personnel
- When switching back to commissioning, the operator-in-charge ensures that the operational conditions are restored and search-and-evict is conducted following the established procedures

# “SRF High Bay” Constructed at MSU

## Infrastructure Investment for FRIB Construction & SRF Research




Objective Measures	Date
Ready-for-equip.	01/2014
Beneficial occu.	05/2014
Clean 1 <sup>st</sup> cavity	07/2014
Coord. measure.	09/2014
Degassing furnace	10/2014
Etch 1 <sup>st</sup> Cavity	12/2014
Cryogenics system	09/2015
RF test 1 <sup>st</sup> cavity	11/2015
Vertical test area	01/2016
Cryomodule test	09/2016

- **Production throughput:**
  - 5 cavity per week
  - > 1 coldmass per month

# MSU Funded Cryogenics Assembly Building and SRF Electropolishing Facility Proceeding

- Cryogenics Assembly Building (CAB) Beneficial Occupancy Date August 2019
  - Cryogenics team to fabricate experimental distribution components
  - SC magnet team to assemble SCD1 and SCD2 magnets
  - Cryomodule team to conduct cryomodule maintenance
- Electro-polishing (EP) expected to be established at MSU early 2020 for FRIB upgrade & research
  - One  $\beta=0.65$  elliptical cavity EP processed at ANL
  - One  $\beta=0.65$  elliptical cavity to be BCP processed at MSU in May 2019



# MSU Cryogenic Initiative Addresses National Need

## Design of Large Cryogenic Plants and Training of Cryogenic Engineers



- Educate and train future cryogenic engineers and systems innovators
- Develop and maintain a cryogenic system knowledge base of cryogenic technology and skills;
- Investigate, propose, and foster efficient cryogenic process designs, and research of advanced cryogenic technologies;
- Maintain a knowledge base to operate unsupported equipment.
- Led by Prof. Rao Ganni (formerly Jefferson Laboratory)
- 14 engineering students enrolled in first class, fall 2017 (5 graduate, 9 undergraduate)



College of Engineering  
MICHIGAN STATE UNIVERSITY



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University


# Summary



**Facility for Rare Isotope Beams**  
U.S. Department of Energy Office of Science  
Michigan State University

# Schedule Integrated and On Track

## Focusing on Critical Path; Accelerating Commissioning Schedule



# We Thank the SRF Community for Your Help in Enabling FRIB Development

- Help from some key SRF experts in critical efforts and important advice to keep FRIB SRF development on track
  - Weekly SRF teleconferences continuously from 2011 (until today with weekly participation from A. Facco and R. Laxdal; earlier days P. Kneisel)
- Benefits from exchanges, visits, workshops and conferences
  - SRF conferences
  - TTF meetings
  - Visits to CEA Saclay and other laboratories
- Collaborations with other laboratories
  - TRIUMF, JLab, FNAL, ...
- Work-for-others contracts with other laboratories
  - JLab, ANL, ...
- Industrial providers pertaining to accelerator and SRF establishments
- We intend to return the favor by sharing with the community our lessons learned and experiences gained

# We Cannot Build FRIB Alone and Are Working with the Best in US and Worldwide

- Argonne National Laboratory
  - Liquid lithium charge stripper; stopping of ions in gas; fragment separator design; beam dynamics; SRF



- Brookhaven National Laboratory
  - Radiation-resistant magnets; plasma charge stripper



- Fermilab
  - Diagnostics



- Jefferson Laboratory
  - Cryogenics; SRF



- Lawrence Berkeley National Laboratory
  - ECR ion source; beam dynamics



- Oak Ridge National Laboratory
  - Target facility; beam dump R&D; cryogenic controls



- Stanford National Accelerator Lab
  - Cryogenics



- Sandia
  - Production target

- Budker Inst. of Nuclear Physics (Russia)
  - Production target
- GANIL (France)
  - Production target
- GSI (Germany)
  - Production target
- INFN Legnaro (Italy)
  - SRF
- KEK (Japan)
  - SRF technology; SC solenoid magnets
- RIKEN (Japan)
  - Charge strippers
- Soreq (Israel)
  - Production target
- Tsinghua University & CAS (China)
  - RFQ
- TRIUMF (Canada)
  - SRF; beam dynamics



# Conclusion

- Nearly five years after the start of technical construction, FRIB is progressing on schedule and on cost, with beam commissioning completed through the first 15 of 46 superconducting cryomodules, and with heavy ions of Ne, Ar, Kr and Xe accelerated above 20 MeV/u.
- The next phase of beam commissioning (ARR4) scheduled after March 2020 aims at accelerating these heavy ion beams to about 200 MeV/u using the 15 QWR CMs and 24 HWR CMs.
- Operations for scientific users is expected to start as planned in 2022.



# Co-authors

- J. Wei<sup>#</sup>, H. Ao, S. Beher, B. Bird, N. Bultman, F. Casagrande, D. Chabot, W. Chang, S. Cogan, C. Compton, J. Curtin, E. Daykin, K. Davidson, K. Elliott, A. Facco<sup>1</sup>, A. Fila, V. Ganni, A. Ganshyn, P. Gibson, T. Glasmacher, I. Grender, W. Hartung, L. Hodges, K. Holland, H.-C. Hseuh, A. Hussain, M. Ikegami, S. Jones, T. Kanemura, S.-H. Kim, M. Konrad, P. Knudsen, R.E. Laxdal<sup>2</sup>, J. LeTourneau, Z. Li, S. Lidia, G. Machicoane, P. Manwiller, F. Marti, T. Maruta, E. Metzgar, S. Miller, D. Morris, C. Nguyen, K. Openlander, P. Ostroumov, A. Plastun, J. Popielarski, L. Popielarski, J. Priller, M. Reaume, H. Ren, T. Russo, K. Saito, M. Shuptar, J. Stetson, D. Victory, R. Walker, X. Wang, J. Wenstrom, M. Wright, M. Xu, T. Xu, Y. Yamazaki, Q. Zhao, S. Zhao, Facility for Rare Isotope Beams, Michigan State University, East Lansing, MI, USA
- K. Dixon, M. Wiseman, Thomas Jefferson National Laboratory, Newport News, VA, USA
- M. Kelly, Argonne National Laboratory, Argonne, IL, USA
- K. Hosoyama, KEK, Tsukuba, Japan
- <sup>1</sup>also at INFN - Laboratori Nazionali di Legnaro, Legnaro (Padova), Italy
- <sup>2</sup>also at TRIUMF, Vancouver, Canada
- <sup>3</sup>also at Argonne National Laboratory, Argonne, IL, USA



# Acknowledgements

- We thank the FRIB Accelerator Systems Advisory Committee for their valuable guidance, colleagues who participated in FRIB accelerator peer reviews including G. Ambrosio, J. Anderson, D. Arenius, W. Barletta, G. Bauer, G. Biallas, J. Bisognano, S. Bousson, P. Brindza, S. Caspi, M. Champion, D. Cossairt, M. Crofford, C. Cullen, D. Curry, R. Cutler, G. Decker, J. Delayen, J. Delong, G. Dodson, J. Donald, H. Edwards, J. Error, J. Fuerst, T. Khabiboulline, F. Kornegay, K. Kurukawa, J. Galambos, J. Galayda, G. Gassner, P. Ghoshal, J. Gilpatrick, C. Ginsburg, S. Gourlay, M. Harrison, S. Hartman, S. Henderson, G. Hoffstaetter, J. Hogan, S. Holmes, M. Howell, P. Hurh, R. Kersevan, A. Hodgkinson, N. Holtkamp, H. Horiike, C. Hovater, H. Imao, R. Janssens, R. Keller, J. Kelley, P. Kelley, J. Kerby, S.H. Kim, A. Klebaner, J. Knobloch, R. Lambiase, M. Lamm, Y. Li, C. LoCocq, C. Luongo, K. Mahoney, J. Mammosser, T. Mann, W. Meng, N. Mokhov, G. Murdoch, J. Nolen, W. Norum, H. Okuno, S. Ozaki, R. Pardo, S. Peggs, R. Petkus, C. Pearson, F. Pellemoine, T. Peterson, C. Piller, J. Power, T. Powers, J. Preble, J. Price, D. Raparia, J. Rathke, A. Ratti, T. Roser, M. Ross, R. Ruland, J. Sandberg, R. Schmidt, W.J. Schneider, D. Schrage, S. Sharma, I. Silverman, K. Smith, J. Sondericker, W. Soyars, C. Spencer, R. Stanek, M. Stettler, W.C. Stone, J. Stovall, H. Strong, L.T. Sun, Y. Than, J. Theilacker, Y. Tian, M. Thuot, J. Tuozzolo, V. Verzilov, R. Vondrasek, P. Wanderer, K. White, P. Wright, H. Xu, L. Young, and A. Zaltsman, and colleagues who advised and collaborated with the FRIB team including A. Burrill, A.C. Crawford, K. Davis, X. Guan, P. He, Y. He, A. Hutton, P. Kneisel, R. Ma, K. Macha, G. Maler, E.A. McEwen, S. Prestemon, J. Qiang, T. Reilly, R. Talman, J. Vincent, X.W. Wang, J. Xia, Q.Z. Xing, and H.H. Zhang.
- The FRIB accelerator design is executed by a dedicated team of the FRIB Accelerator Systems Division with close collaboration with the Experimental Systems Division headed by G. Bollen, the Conventional Facility Division headed by B. Bull, the Chief Engineer's team headed by D. Stout, and supported by the project controls, procurements, ES&H of the FRIB Project, by NSCL, and by MSU.
- Work supported by the U.S. Department of Energy Office of Science under Cooperative Agreement DE-SC0000661.



# References

- [1] J. Wei *et al.*, *International Journal of Modern Physics E* **28**, 1930003 (2019).
- [2] J. Wei *et al.*, in *Proc. HIAT 2012, Chicago*, p. 8.
- [3] M. Johnson *et al.*, in *Proc. IPAC 2012, New Orleans*, p. 2507.
- [4] S. Miller *et al.*, "FRIB cavity and cryomodule performance, comparison with the design and lessons learned," WETEA5, these proceedings.
- [5] T. Xu *et al.*, in *Proc. SRF 2017, Lanzhou*, p. 345.
- [6] V. Ganni *et al.*, in *Proc. CEC-ICMC 2013*, **59**, p. 323.
- [7] A. Facco *et al.*, in *Proc IPAC 2012, New Orleans*, p. 61.
- [8] A. Facco *et al.*, in *Proc. SRF 2013, Paris*, p. 873.
- [9] S. Stark *et al.*, in *Proc. LINAC 2016, East Lansing*, p. 535.
- [10] S. Miller *et al.*, in *Proc. SRF 2013, Paris*, p. 825.
- [11] M. Ikegami, in *Proc. IPAC 2015, Richmond*, p. 2418.
- [12] F. Casagrande, in *IPAC 2015, Richmond*, THYB1.
- [13] C. Compton *et al.*, "The FRIB superconducting cavity production status and findings concerning surface defects," THP098, these proceedings.
- [14] E. Metzgar *et al.*, "Summary of FRIB cavity processing in the SRF coldmass processing facility and lessons learned," TUP093, these proceedings.
- [15] W. Hartung *et al.*, "Performance of FRIB production quarter-wave and half-wave resonators in Dewar certification tests," THP061, these proceedings.
- [16] K. Elliott *et al.*, "Experiences of superconducting radio frequency coldmass production for the FRIB linear accelerator," TUP092, these proceedings.
- [17] W. Chang *et al.*, "Progress in FRIB cryomodule bunker tests," THP062, these proceedings.
- [18] J. Popielarski *et al.*, "FRIB coupler performance and lessons learned," MOP071, these proceedings.
- [19] K. Saito *et al.*, "FRIB solenoid package in cryomodule and local magnetic shield," MOP072, these proceedings.
- [20] M. Xu *et al.*, "FRIB LS1 cryomodule's solenoid commissioning," TUP089, these proceedings.
- [21] C. Compton *et al.*, "Production status of superconducting cryomodules for the Facility for Rare Isotope Beams," TUP091, these proceedings.
- [22] S. Kim *et al.*, "Performance of quarter wave resonators in the FRIB Superconducting driver linear accelerator", TUP090, these proceedings.
- [23] D. Morris *et al.*, in *Proc. IPAC 2018, Vancouver*, p. 1765.
- [24] J. Vincent *et al.*, *Nucl. Instrum. Meth. Phys. Res. A* **643**, p. 11 (2011).
- [25] J. Crisp *et al.*, in *Proc. NAPAC 2013, Pasadena*, p. 1187.
- [26] Z. Liu *et al.*, *Nucl. Instrum. Meth. Phys. Res. A* **767**, p. 262 (2014)
- [27] 7<sup>th</sup> MicroTCA Workshop for Industry and Research, Hamburg (2018), <https://mtcaws.desy.de>
- [28] S. Cogan *et al.*, in *Proc. IBIC 2016, Barcelona*, p. 572.
- [29] M. Konrad, in *Proc. PCaPAC 2016, Campinas*, p. 105.
- [30] A. Li *et al.*, in *Proc. LINAC 2018, Beijing*, p. 336.
- [31] S. Lidia, in *Proc. IBIC 2014, Monterey*, p. 239.
- [32] A. Li *et al.*, in *Proc. LINAC 2016, East Lansing*, p. 956.
- [33] M. Konrad *et al.*, in *Proc. PCaPAC 2016, Campinas*, p. 145.
- [34] E. Pozdeyev *et al.*, in *Proc. LINAC 2018, Beijing*, p. 615.
- [35] P. Ostroumov *et al.*, *Phys. Rev. Accel. Beams* **22**, 040101 (2019).
- [36] L. Popielarski *et al.*, in *Proc. LINAC 2014, Geneva*, p. 954.



Thank You!

