



19th International Conference on RF Superconductivity

June 30th – July 5th 2019



Successful Beam Commissioning in STF-2 Cryomodules for ILC

Y. Yamamoto (KEK) on behalf of STF-2 beam commissioning group

STF-2 Beam Commissioning Group

Y. Yamamoto[#], E. Kako, T. Shishido, K. Umemori, H. Sakai, T. Saeki, T. Konomi, T. Matsumoto, S. Michizono, M. Egi, M. Akemoto, D. Arakawa, H. Katagiri, M. Kawamura, F. Qiu, H. Nakajima, T. Miura, H. Hayano, M. Fukuda, Y. Honda, N. Nakamura, T. Miyajima, T. Obina, M. Shimada, A. Aryshev, M. Kuriki, S. Matsuba, S. Notsu, K. Sakaue, H. Nakai, Y. Kojima, K. Hara, T. Honma, K. Nakanishi, H. Shimizu, Y. Kondou, A. Yamamoto, N. Kimura, S. Araki, Y. Morikawa, T. Sanami, T. Oyama, S. Takahara

KEK, Hiroshima Univ., Univ. of Tokyo



東京大学
THE UNIVERSITY OF TOKYO



SRF 19 @Dresden






Outline

- ◆ **ILC project and status**
- ◆ **STF and STF-2 project**
- ◆ **Construction of STF-2 accelerator**
- ◆ **Maximizing Accelerating Gradient**
- ◆ **Comparison of cavity voltage and beam energy**
- ◆ **Heat load measurement**
- ◆ **History of Radiation Level**
- ◆ **Troubles, Next step, Summary**

ILC project

- Higgs factory machine (250 GeV @ E_{CM})
- Superconducting cavity/cryomodule technology as mass production
 - Based on TESLA technology
 - ~1000 Cryomodules (challenging number, but not impossible!)
- Nano beam technology
- Candidate site: Kitakami in Japan



ILC Spec.	E_{acc}	Q_0
Vertical Test	35 MV/m	0.8×10^{10}
Cryomodule test	31.5 MV/m	1.0×10^{10}

>90% (successful rate)

ILC Status (just recently)

Mar/2019

“Expressions of interest” by MEXT
ICFA released statement



Apr/2019

LC Community Meeting @Lausanne



May/2019

European Strategy Open Symposium @Granada
Int. WG established




Oct/2019


LCWS2019 held in Sendai/Japan



Aug/2019
ICFA/LCB held in Toronto



SRF 19 @Dresden



ILC Status (just recently)

Mar/2019

“Expressions of interest” by MEXT
ICFA released statement




Apr/2019

LC Community Meeting @Lausanne

May/2019

European Strategy Open Symposium @Granada
Int. WG established




Oct/2019

LCWS2019 held in



SRF 19 @Dresden




Outline

- ◆ ILC project and status
- ◆ **STF and STF-2 project**
- ◆ Construction of STF-2 accelerator
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Superconducting RF Test Facility (STF) in KEK

STF-1 (4 cavities) in 2008




- ◆ Started from 2006
- ◆ Available for half size of CM
- ◆ Multi-beam klystron
- ◆ Cryogenics system
- ◆ EP system
- ◆ VT system


S1-Global (4+4 cavities) in 2010




Quantum Beam (2 cavities) in 2012
Capture CM in STF-2 accelerator




70 m linac



Superconducting RF Test Facility (STF) in KEK



- ◆ Started from 2006
- ◆ Available for half size of CM
- ◆ Multi-beam klystron
- ◆ Cryogenics system
- ◆ EP system
- ◆ VT system




S1-Global (4+4 cavities) in 2010

Purpose: Technology demonstration of superconducting cavity/cryomodule for ILC




Quantum Beam (2 cavities) in 2012
Capture CM in STF-2 accelerator




STF-2 project and STF-2 accelerator



STF Cavity



STF-II power coupler



Slide-jack tuner



STF Cavity Package

Dump 2

Bend 2

STF-2 Cryomodules
12 cavities
(Constructed in F.Y.2014)

Dump 1

Bend 1

Capture Cryomodule
2 cavities
(Constructed in F.Y.2012)

RF Gun incl.
photo-cathode


Cooldown	Date	Content
1	Oct/2014 ~ Dec/2014	Low power test
2	Oct/2015 ~ Dec/2015	Single cavity operation, performance check
3	Sep/2016 ~ Nov/2016	Eight cavities operation, LFD and heat load meas., LLRF study
4	Jan/2019 ~ Mar/2019	Beam commissioning, Machine study

Operational condition


- ◆ RF: 1.65 msec/5 Hz (ILC/TDR)
- ◆ Temperature: 2K in liq. Helium
- ◆ As max. E_{acc} as possible for STF-2 CM

STF-2 project and STF-2 accelerator



STF Cavity



STF-II power coupler



Slide-jack tuner



STF Cavity Package

Dump 2

Bend 2

Cooldown	Date	Content
----------	------	---------

Purpose: Beam operation satisfied ILC specification

2	Oct/2015 ~ Dec/2015	Single cavity operation, performance check
3	Sep/2016 ~ Nov/2016	Eight cavities operation, LFD and heat load meas., LLRF study
4	Jan/2019 ~ Mar/2019	Beam commissioning, Machine study

Operational condition

- ◆ RF: 1.65 msec/5 Hz (ILC/TDR)
- ◆ Temperature: 2K in liq. Helium
- ◆ As max. E_{acc} as possible for STF-2 CM

STF-2 Cryomodules
12 cavities
(Constructed in F.Y.2014)

Bend 1

Dump 1

Capture Cryomodule
2 cavities
(Constructed in F.Y.2012)

RF Gun incl.
photo-cathode

Outline

- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ **Construction of STF-2 accelerator**
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Construction of STF-2 accelerator


Preparation for RF Gun operation



Installation of beam dump #2




Alignment work



Connection of beamlines



Beampipe reconnection




Beamline construction completed!



TUP104 by H. Sakai

Jan/2019



Outline


- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ Construction of STF-2 accelerator
- ◆ **Maximizing Accelerating Gradient**
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Ready for beam operation

We skipped RF conditioning with short pulse in 3rd cooldown test, because schedule was very tight!

- ✓ Tuning cavity frequency
- ✓ RF conditioning with short pulse (900 + 100 μ s)
- ✓ RF conditioning with long pulse (900 + 800 μ s)
- ✓ Fine tuning by piezo ($\Delta f \sim \pm 50$ Hz)
- ✓ Closed-loop operation
- ✓ RF Gun/Laser system operation
- ✓ Beam commissioning

Summary of Accelerating Gradient in STF-2 CMs




CAV#5, #6, #7, and #9 are not used, because waveguide system is not available

Maximizing accelerating gradient

Power distribution adjustment by variable hybrid

Best parameters after adjustment

PHASE SHIFTER (CM1,CM2a)										REMOTE
Position										
CH	busy	monitor	set	stop	step	+	-	ccw	cw	
01:CAV1 HB	●	-291	0	STOP	10	+	-	●	●	
02:CAV2 HB	●	-3327	0	STOP	50	+	-	●	●	
03:CAV3 HB	●	418	0	STOP	10	+	-	●	●	
04:CAV4 HB	●	-1548	0	STOP	0	+	-	●	●	
05:CAV1 PS	●	-140551	0	STOP	5000	+	-	●	●	
06:CAV2 PS	●	-99329	0	STOP	40000	+	-	●	●	
07:CAV3 PS	●	-42759	0	STOP	5000	+	-	●	●	
08:CAV4 PS	●	68375	0	STOP	0	+	-	●	●	
09:CAV8 HB	●	-2870	0	STOP	10	+	-	●	●	
10:CAV10 HB	●	-275	0	STOP	10	+	-	●	●	
11:CAV11 HB	●	-4348	0	STOP	10	+	-	●	●	
12:CAV12 HB	●	3980	0	STOP	50	+	-	●	●	
13:CAV8 PS	●	-62447	0	STOP	10000	+	-	●	●	
14:CAV10 PS	●	6235	6235	STOP	40000	+	-	●	●	
15:CAV11 PS	●	31290	0	STOP	20000	+	-	●	●	
16:CAV12 PS	●	-58844	0	STOP	20000	+	-	●	●	



Variable hybrid/Phase shifter attached for each cavity

Cavity Monitor (CM1,CM2a)

	#1	#2	#3	#4	#8	#10	#11	#12
Pf (W):	86.63kW	87.01kW	70.42kW	41.71kW	83.97kW	63.13kW	56.69kW	51.13kW
Pf Eacc(MV/m):	39.25	39.00	35.42	0.00	37.50	33.92	32.21	30.25
Pt(W):	14.06W	10.09W	7.33W	469.67uW	12.97W	7.99W	9.46W	6.46W
Pt Eacc(MV/m):	36.71	35.41	33.57	0.20	36.46	32.69	31.42	30.32
Electron(mV):	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
Arc(mV):	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

He flow rate

2K:	55.225 m ³ /hour
5K:	0.000 m ³ /hour

Heat Load

2K:	64.429 W
-----	----------

He pressure

2K:	3.01 kPa
4K:	124.41 kPa

He level

4K:	51.29 %
2K:	54.41 %
CM2a End:	22.50 %

Vacuum

Capture Upstream	5.83E-7 Pa
Capture Downstream	2.04E-7 Pa
Capture Input coupler	3.70E-7 Pa
Capture Inner conductor	1.27E-8 Pa
CM1 Upstream	2.19E-7 Pa
CM1 Input coupler	2.08E-6 Pa
CM1 Inner conductor	2.30E-8 Pa
CM2a Downstream	2.31E-7 Pa
CM2a Input coupler	2.59E-6 Pa
CM2a Inner conductor	4.05E-8 Pa

Power

KLY3 上 Pf	2.36MW
KLY3 下 Pf	2.31MW
Pt Eacc sum	236.57MV/m
Pt Eacc ave.	33.80MV/m
Input Volt	3.15V
Feedback	ON

Temperature

4K Pot:	4.64 K
2K Pot:	1.69 K
80K anchor #1:	124.350 K
80K anchor #2:	130.250 K


Radiation

	Up	Mid	Down
High:	935.390 uSv/h	979.485 uSv/h	796.114 uSv/h
Low:	4.607 mSv/h	8.194 mSv/h	25.183 mSv/h

Outline

- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ Construction of STF-2 accelerator
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Accelerating gradient estimated from beam energy






Outline

- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ Construction of STF-2 accelerator
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ **Heat load measurement**
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Dynamic heat load in STF-2 CM

- Estimated from helium mass flow rate
- Meas. Flow: Static → Dynamic (cavity) → Dynamic (coupler) → Static
- Systematic error: 20~30% (RF duty < 1%)
- Well-reproducible for three measurements
- Consistent with ILC spec. within error bar



ILC spec.	E_{acc}	Q_0
Cryomodule test	31.5 MV/m	1.0×10^{10}

Outline

- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ Construction of STF-2 accelerator
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary


History of radiation level



High sensitivity detector




Low sensitivity detector




MAR-781/-782


Reconnected beampipe




X-ray Onset Gradient in STF-2 CMs



Radiation level for Cavity #2 in STF-2 CM1/2a



Radiation level for Cavity #8 in STF-2 CM1/2a



- Some cavities had higher radiation level in this test
- One cavity had a little bit higher after beam commissioning
- Other cavities had same level


Outline

- ◆ ILC project and status
- ◆ STF and STF-2 project
- ◆ Construction of STF-2 accelerator
- ◆ Maximizing Accelerating Gradient
- ◆ Comparison of cavity voltage and beam energy
- ◆ Heat load measurement
- ◆ History of Radiation Level
- ◆ Troubles, Next step, Summary

Troubles in this commissioning

- **Cooling water system down due to defect of pumping system (solved)**
- **IEGT fault in modulator for multi-beam klystron (solved)**
- **Spark in waveguide system for multi-beam klystron (solved)**
- **Breakdown of resistor in DRFS modulator (solved)**
- **Temporary (twice) warm-up/cool-down by cryogenic system fault (solved)**
- **Not worked tuner system for CAV#4 (solved)**
- **QF/QD cable mismatch (solved)**
- **Cavity quench after GV opened (solved)**
- **Worse vacuum at upstream beamline of Capture cryomodule (should be baked)**

We lost 5 days due to these troubles!



Every trouble was solved, but some maintenance work is necessary till next beam operation

Towards next beam commissioning in F.Y. 2020

- ❑ Cavity exchange in CM2a
- ❑ Laser system upgrade (not easy!)
- ❑ Improvement of beam dump system
- ❑ Power upgrade for RF Gun
- ❑ RF pulse data storage in last 30 sec for CM1/2a
- ❑ IEGT board for klystron #3
- ❑ Power control system upgrade for DRFS
- ❑ Pumping system repair for cryogenics
- ❑ Maintenance for cooling water system


Challenging work for us (first time!)

Cause for very low beam current

Request from radiation security center

New surface treatment technology

- N-infusion
- Low temp. baking



Summary

- ◆ Beamline in STF-2 accelerator was successfully constructed
- ◆ Accelerating gradient of 33.1 MV/m estimated from beam energy was achieved!
- ◆ Heat load measurement was well-reproducibly done, consistent with ILC spec.
- ◆ Radiation level increased for some cavities, but performance recovered
- ◆ Defect of ultra-high vacuum rotary feedthrough for CAV#4 tuner system
- ◆ Cavity exchange in CM2a will be done in F.Y. 2019

Announcement

LCWS2019 will be held in Sendai!

<http://epx.phys.tohoku.ac.jp/LCWS2019/>





Thank you very much for your attention!

Acknowledgement: K. Harada, M. Tawada, M. Masuzawa, S. Nagahashi, M. Asano, S. Imada, H. Yamada, T. Tainaka, S. Ishihara, K. Ishimoto, N. Numata, K. Tsutsumi, T. Okada, M. Iitake, A. Hayakawa, R. Terajima